

ATTACHMENT 7

Superfund Record of Decision: Hagen Farm Superfund Site, WI March 1991



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY REGION 5 230 SOUTH DEARBORN ST. CHICAGO, ILLINOIS 60604

Logged in File A4-1
15340. XX

SK-TERMENT

MAR 07 1991

REPLY TO ATTENTION OF:

CERTIFIED MAIL RETURN RECEIPT REQUESTED

Waste Management of Wisconsin, Inc. c/o Ms. Anne Straw Suite 1000 Two Westbrook Corporate Center P.O. Box 7070 Westchester, Illinois 60154

RE: Hagen Farm Superfund Site Dane County, Wisconsin

Dear Ms. Straw:

And ROD

Enclosed is a unilateral Administrative Order issued by the United States Environmental Protection Agency (U.S. EPA) under Section 106 of the Comprehensive Environmental Response, Compensation and Liability Act of 1980, as amended by the Superfund Amendments and Reauthorization Act of 1986 (CERCIA), 42 U.S.C. 9601, et seq.

Please note that the Effective Date of the Administrative Order (Order) is March 15, 1991. Also, please note that a conference has been scheduled for March 13, 1991, 10:00 am in the northwest corner conference room on the 11th floor, U.S. EPA Region V, 230 South Dearborn Street, Chicago, Illinois. The purpose of the meeting is to discuss the Administrative Order and its applicability to your company.

If you have any questions regarding the Order, please do not hesitate to contact Jae B. Lee, Remedial Project Manager, at (312) 886-4749, or Jeffrey A. Cahn, Assistant Regional Counsel, at (312) 886-6670.

Sinceraly yours Director, Waste Management Division

DATE RECEIVED/SENT Enclosure BY: DEE BRNCICH SITE _ cc: (w/encl) P. Didier CC/ROUTE: JD, GM. HK. DO. RO.

FILE SYSTEM: PROJECT/SITE

FILE CODE: -W/ATTACH 3_ W/O ATTACH

Printed on Recycled Paper

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY REGION V

IN MATTER OF:

HAGEN FARM SUPERFUND SITE DANE COUNTY, WISCONSIN

ADMINISTRATIVE ORDER
PURSUANT TO SECTION 106
OF THE COMPREHENSIVE
ENVIRONMENTAL RESPONSE,
COMPENSATION, AND
LIABILITY ACT OF 1980, RESPONDENTS:
AS AMENDED

WASTE MANAGEMENT OF WISCONSIN, INCORPORATED,

and

UNIROYAL PLASTICS COMPANY, INCORPORATED.

I. PREAMBLE

The following Administrative Order ("Order") is issued on this date to the Respondents pursuant to the authority vested in the President of the United States by Section 106(a) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980, 42 U.S.C. Section 9606(a), as amended by the Superfund Amendments and Reauthorization Act of 1986, Pub. L. 99-499 ("CERCIA"), and delegated to the U.S. Environmental Protection Agency ("U.S. EPA" or "Agency") by Executive Order No. 12580, January 23, 1987, 52 Federal Register 2923, and further delegated to the Regional Administrator by U.S. EPA Delegation No. 14-14-B, issued February 26, 1987, and further delegated to the Director of the Waste Management Division, Region V by Delegation No. 14-14-B, issued September 14, 1987. Pursuant to Section 106(a) of CERCIA, 42 U.S.C. Section 9606(a), notice of issuance of this Order has been given to the State of Wisconsin.

This Administrative Order requires the Respondents, and each of them, to undertake remedial action activities at the Hagen Farm site located in Dane County, Wisconsin, and described in greater detail below, (the "Facility"), to abate an imminent and substantial endangerment to the public health or welfare or the environment that may be presented by the release or threat of a release of hazardous substances present at the Facility.

II.

PARITIES BOUND

This Administrative Order applies to and is binding upon the Respondents, their successors and assigns. The Respondents shall provide a copy of this Administrative Order to each engineer or contractor hired to perform the work required by this Administrative Order. The Respondents shall also require that any contractor provide a copy of this Administrative Order to each subcontractor retained to perform any part of the work required by this Administrative Order.

III.

DEFINITIONS

Whenever the following terms are used in this Administrative Order or the Appendices attached hereto, the definitions specified in this Section shall apply:

- A. "CERCIA" means the Comprehensive Environmental Response,
 Compensation, and Liability Act of 1980, as amended by the Superfund
 Amendments and Reauthorization Act of 1986, Pub. L. 99-499.
- B. "Engineer(s)" means the company or companies retained by the Respondents to prepare the plans and implement the remedial action required pursuant to this Administrative Order.

- C. "Facility" means the "facility" as that term is defined at Section 101(9) of CERCIA, 42 U.S.C. Section 9601(9), where disposal of hazardous substances was conducted; which Facility is located in Dane County, Wisconsin, and is known as the Hagen Farm Superfund Site.
- D. "Hazardous substance" shall have the meaning provided in Section 101(14) of CERCIA, 42 U.S.C. Section 9601(14).
 - E. "WDNR" means the Wisconsin Department of Natural Resources.
- F., "National Contingency Plan" shall be used as that term is used in Section 105 of CERCIA, 42 U.S.C. Section 9605.
- G. "Operable Unit" as it applies to this Facility is a source control action for remediation of on-site wastes and contaminated sub-surface soils.
 - H. "Parties" means the United States of America and the Respondents.
- I. "Record of Decision" or "ROD" means the U.S. EPA approved remedy selected to be implemented at the Facility, signed by the Regional Administrator of U.S. EPA, Region V, on September 17, 1990, concurred in by the State, and attached as Appendix I.
- J. "Respondents" means Waste Management of Wisconsin, Incorporated ("WMWI") and Universal Plastics Company, Incorporated ("Universal").
- K. "Response Costs" means any costs incurred by U.S. EPA pursuant to 42U.S.C. Sections 9601 et seq.
- L. "Section 106 Administrative Record" means the Administrative Record which includes all documents considered or relied upon by U.S. EPA in preparation of this Administrative Order. The Section 106 Administrative Record Index is a listing of all documents included in the Section 106 Record, as set forth in Appendix II.
 - M. "State" means the State of Wisconsin.

- N. "United States" means the United States of America.
- O. "Work" means the activities to be undertaken by Respondents in accordance with this Administrative Order and appendices hereto.

IV.

FINDINGS OF FACT AND DETERMINATIONS

- A. The Hagen Farm site is a Facility within the meaning of Section 101(9) of CERCIA, 42 U.S.C. Section 9601(9). The Facility is located at 2318 County highway A, Dane County, Wisconsin.
- B. The Facility consists of a total of approximately 10 acres in an area of rural surrounding that is dominated largely by sand and gravel mining and agriculture. Soil and gravel mining operations are located northwest, northeast and south of the Facility. The Stoughton Airfield is located adjacent to the northwest corner of the Facility. County Highway "A" passes just south of the Facility.
- C. The Facility was operated as a sand and gravel pit prior to the late 1950s. The gravel pit then used for disposal of waste material from the late 1950s to the mid-1960s. The former disposal area encompasses approximately five acres of land located in the southwestern portion of the Facility which previously had been used as a gravel quarry. The quarry was believed to be approximately 14 to 18 feet deep at the time of waste disposal. The Facility operator accepted municipal wastes, waste solvents and other various organic materials including acetone, butyl acetate, 1-2-dichloroethylene, tetrahydrofuran, solid vinyl, sludge material containing methylethyl ketone and xylenes, and toluene. In a 103(c) notification submitted to the U.S. EPA by Uniroyal, Inc., in June 1981, Uniroyal indicated that F003 and F005 wastes,

which are hazardous wastes within the meaning of the Resource Conservation and Recovery Act ("RCRA"), 42 U.S.C. 6901, also were disposed of at the Facility.

- D. During the period that the Facility was operated as a disposal facility, the property was owned by Nora Sundby, who is now deceased. The Facility was operated by City Disposal Corporation ("City Disposal"), an antecedent corporation of Waste Management of Wisconsin ("WMWI"). City Disposal was also the transporter of much of the waste that was deposited at the Facility. On November 30, 1977, the Facility was conveyed by the estate of Ms. Sundby to Orrin N. and Ida Mae Hagen. On February 24, 1987, Orrin Hagen conveyed ownership of the Facility to WMVI. The Facility property is currently owned by WMWI. The U.S. Rubber Company Plant at Stoughton, Wisconsin, generated industrial waste, some of which was disposed at the Facility from sometime in 1962 until August of 1966. The U.S. Rubber Company subsequently changed its name to Uniroyal, Incorporated. The Stoughton plant is now owned and operated by Uniroyal Plastics Company, Inc., which is the successor in interest to Uniroyal, Inc. in this matter. Waste materials generated at the Stoughton plant which were or may have been disposed at the Facility included solid chunks of vinyl and some organic solvents, such as toluene, acetone, xylene, tetrahydrofuran, and methyl ethyl ketone.
- E. Beginning in November 1980, in response to complaints received from local residents, the WDNR began conducting groundwater sampling at nearby private water supply wells. Sampling of the on-Site monitoring wells during the period 1980-1986 indicated certain organic compounds were present in the groundwater, including benzene, ethylbenzene, tetrahydrofuran, xylenes, and toluene. In addition, nearby private water supplies on adjacent properties have also shown detectable levels of volatile organic compounds ("VOCs"). The

private wells located on the Facility had been impacted by acetone, tetrahydrofuran, vinyl chloride, xylene, trans 1,2-dichlorethene, and trichloroethylene.

- F. In 1983, the State of Wisconsin brought an enforcement action for abatement of a public nuisance against WMWI and Universal. At the same time, nearby residents at the Facility brought a civil action against WMWI and Universal, seeking civil damages for reduced property values and potential health hazards resulting from groundwater and well contamination. The State of Wisconsin obtained a dismissal of its 1983 enforcement action against WMWI and Universal after the Facility was listed on the National Priorities List ("NPL"). In 1986, the parties to civil litigation brought by the nearby residents to the Facility against WMWI and Universal reached a settlement.
- G. The Facility was proposed for inclusion on the NPL on September 18, 1985. The Facility was placed on the NPL in July of 1987. Subsequently, WMWI and Uniroyal, the two Respondents named by U.S. EPA in connection with the Facility to date, entered into an Administrative Order by Consent (U.S. EPA Docket No. VW 87-C-016, dated September 14, 1987) (the "Consent Order") with the U.S. EPA and the WDNR. In the Consent Order, WMWI and Uniroyal agreed to conduct a Remedial Investigation and Feasibility Study ("RI/FS") at the Facility. Accordingly, in July of 1988, upon U.S. EPA approval, in consultation with the WDNR, of the required Work Plans, fieldwork at the Facility commenced.
- H. Two operable units, which are being conducted concurrently, have been defined for the Facility. Operable Unit ("OU") I, which is the Source Control Operable Unit ("SCOU"), is intended to address waste refuse and sub-

surface soils ("Waste/sub-Soils") at disposal area A and the two smaller disposal areas B and C. OU II, which is the Groundwater Control Operable Unit ("GCCU"), is intended to address the contaminated groundwater at the Facility. The OU approach was agreed upon after discussions among U.S. EPA, WDNR, and Respondents during the early phase of the implementation of the Work Plan for the RI.

- I. The RI for the SCOU was completed in early 1989, and the Technical Memorandum for the SCOU was submitted in March 1989. The RI for the GCOU was initiated in July 1989 and the Technical Memorandum for GCOU was submitted in February 1990. Currently, additional field activities to define the extent of plume migration are ongoing. The RI report for the GCOU, including the Endangerment Assessment, is scheduled for completion in July 1991. The ROD for the GCOU is scheduled for early 1992.
- J. In June, 1990, U.S. EPA provided the FS and the Proposed Plan for the source control remedial action to the public. An opportunity for public comment was provided. Comments were to be submitted in writing to the U.S. EPA by August 10, 1990, or orally at the public meeting held in Stoughton, Wisconsin, on August 2, 1990. The Respondents were allowed to submit comments on the Proposed Plan for the final remedy during this public comment period.
- K. Considering the Proposed Plan for remedial action and the public comments received, U.S. EPA, with concurrence by the State, selected a source control remedy for remediation of on-site waste and sub-surface soils at the Facility. U.S. EPA's decision is summarized in the Record of Decision ("ROD") signed by the U.S. EPA Administrator, Region V, on September 17, 1990. The ROD is attached as Appendix I. The selected remedy includes the following: consolidation of non-native materials from disposal areas B and C into

disposal area A with subsequent backfilling of disposal areas B and C with clean soil material; installation of a WDNR NR 504 solid waste cap over disposal area A after consolidation; <u>In-situ</u> vapor extraction of the waste refuse and sub-surface soils in disposal area A; off-gas treatment through carbon adsorption; installation and maintenance of a fence around disposal areas A, B, and C during remedial activities; and deed and access restrictions to prevent installation of drinking water wells within vicinity of the disposal areas and to protect the cap.

- L. U.S. EPA's ROD includes a discussion of U.S. EPA's reasons for the selection of the source control remedy. The remedial action ("RA") has been determined to be a cost-effective remedial action which provides adequate protection of public health, welfare, and the environment, and meets all Federal and more stringent State ARARs.
- M. Contaminants are being released to the environment through the following pathways: volatilization of contaminants through the soil to the air; direct contact; and release of contaminants from waste, and soils to the groundwater. These releases provide potential for exposure to humans as well as terrestrial and aquatic life.
- N. Analyses of soils, waste, and fill materials performed during the RI revealed the presence of numerous hazardous substances as defined in Section 101(14) of CERCIA, including ethylbenzene, toluene, xylene, 2-butanone, tetrahydrofuran, vinyl chloride, arsenic, lead, and mercury. These contaminants are present in the subsurface soils at and above the water table and continue to be released into the groundwater. Some compounds detected in the soils and waste and their associated maximum concentrations are listed below.

WASTE AND SOIL ANALYTICAL DATA

(ug/kg)

<u>Chemical</u>	Maximum
SEMI-VOLATTLES	
Naphthalene	46
1,4-Dichlorobenzene	280
Diethylphthalate	48
Di-n-Butylphthalate	690
Fluoranthene	67
Butylbenzylphthalate	18,000
bis(2-Ethylhexyl)Phthalate	120,000
Di-n-Octyl Phthalate	5,300
Phenanthrene	67
Unknown Semivolatiles	1,261,985
PESTICIDES/PCBS	
Dieldrin	11.6
4,4'-DDE	18.2
4,41-DDD	128
4,4'-DOT	19.2
PCB-1248	338
PCB-1254	222
PCB-1242	284

O. Preliminary data developed during analyses of the groundwater performed during the RI for the SCOU revealed the presence of numerous hazardous substances as defined in Section 101(14) of CERCIA, including ethylbenzene, toluene, xylene, tetrahydrofuran, 2-Butanone, and metals. Some

compounds detected in groundwater and their associated maximum concentrations are listed below.

GROUNDWATER ANALYTICAL DATA

(ug/l) <u>Chemical</u>	Maximum
VOLATILES	
2-Butanone	4,400,000
Ethylbenzene	4,400
Tetrahydrofuran	630,000
Toluene	550
Vinyl chloride	77
Total Xylenes	35,000
SEMI-VOLATILES	
Naphthalene	8
1,4-Dichlorobenzene	10
Diethylphthalate	5
Phenol	5,600
Benzoic Acid	29,000
Benzyl Alcohol	26
bis(2-Ethylhexyl)Phthalate	34
Di-n-Octyl Phthalate	5
4-Chloro-3-Methylphenol	7
2,4-Dimethylphenol	330
4-Methylphenol	6,100
Bis(2-Chloroisopropyl)Ether	19
METALS	
Arsenic :	25.2

Lead

6

Mercury

6.5

This preliminary groundwater data indicates that the landfill that is part of this Facility is the source of the contamination found in the groundwater.

U.S. EPA anticipates that data regarding contamination of the groundwater will be further developed during the RI for the GCCU.

- P. From the late 1950s to the mid-1960s "hazardous substances" as defined in Section 101(14), of CERCIA, 42 U.S.C. Section 9601(14), were deposited, stored, disposed of, placed, or located at the Facility.
- Q. The past, present, and/or future migration of hazardous substances from the Facility constitute an actual, and/or threatened "release" into the environment as defined in Section 101(22) of CERCIA, 42 U.S.C. Section 9601(22), and may present an imminent and substantial endangerment to the public health or welfare or the environment.
- R. From the late 1950s to the mid-1960s, City Disposal Corporation was the "owner" and/or "operator" of the Facility as defined in Section 101(20) of CERCIA, 42 U.S.C. Section 9601(20), and "owned" and/or "operated" the Facility within the meaning of Section 107(a)(2) of CERCIA, 42 U.S.C. Section 9607(a)(2). City Disposal Corporation was subsequently purchased by Waste Management of Wisconsin, Incorporated. The Facility property is currently owned by WMWI.
- S. The U.S. Rubber Company plant at Stoughton, Wisconsin, generated industrial waste, some of which was deposited at the Facility beginning sometime in 1962 and continuing through August of 1966. The U.S. Rubber company subsequently changed its name to Univoyal, Incorporated. The

Stoughton plant is now owned and operated by Uniroyal Plastics Company,
Incorporated, which is the successor in interest to Uniroyal, Incorporated.

- T. Respondents are "persons" as defined in Section 101(21) of CERCIA, 42 U.S.C. Section 9601(21), and, based upon information available to U.S. EPA, each Respondent generated and/or transported hazardous substances which were disposed of at the Facility, making each Respondent a "liable person" with respect to the Facility within the meaning of Section 107 of CERCIA, 42 U.S.C. Section 9607. The responses to information requests and other documents supporting the Respondents' liability for performance of the actions required by this Administrative Order are contained in the Section 106 Administrative Record for the Administrative Order, which supports the issuance of the Administrative Order under Section 106 of CERCIA. The Index for the Section 106 Administrative Record is attached as Appendix II.
- U. The actions required by this Administrative Order are necessary to protect the public health or welfare or the environment, and are consistent with the National Contingency Plan, 40 CFR Part 300 et seq., as amended.

v.

ORDER

Based upon the foregoing Findings of Fact and Determinations, and pursuant to Section 106(a) of CERCIA, 42 U.S.C. Section 9606(a), it is hereby ordered that Respondents perform the work as described below and in the Scope of Work ("SOW") attached hereto, and made an enforceable part hereof, as Appendix III.

A. Work to be Performed

1. The Respondents shall, within forty-five (45) days of the effective date of this Order, submit to U.S. EPA a Remedial Design and Remedial Action

("RD/RA") Work Plan to implement all portions of the recommended alternative outlined in the Record of Decision for the Facility and in the Scope of Work (Appendix III).

- 2. The RD/RA Work Plan shall be written in sufficient detail to fully address all necessary design parameters of the recommended alternative, shall be consistent with the SOW and shall be consistent with U.S. EPA's June 1986 Superfund Remedial Design and Remedial Action Guidance. In addition, the RD/RA Work Plan shall include, but not be limited to, the following elements:
 - A Field Operating Plan for Waste Consolidation
 - A Contingency Plan for Waste Consolidation

this Order.

- A Sampling and Testing Plan for Clay

 The RD/RA Work Plan and other documents submitted by the Respondents shall

 demonstrate that the Respondents can properly conduct the actions required by
- 3. U.S. EPA shall review and approve/disapprove the RD/RA Work Plan. If the RD/RA Work Plan is acceptable, approval shall be granted, in writing, and the RD/RA Work Plan shall become an integral and enforceable element of this Order. If the RD/RA Work Plan is disapproved, U.S. EPA shall state to the Respondents, in writing, the reasons for disapproval. Respondents shall, within thirty (30) calendar days of receipt of U.S. EPA's letter stating disapproval, incorporate all changes requested by U.S. EPA into the RD/RA Work Plan and submit the Amended RD/RA Work Plan to U.S. EPA. If approved, the Amended RD/RA Work Plan shall become an integral and enforceable element of this Order. Failure to incorporate all changes requested by U.S. EPA into the RD/RA Work Plan shall constitute a violation of the terms of this Order.

- 4. Respondents shall begin implementation of the RD/RA Work Plan immediately upon receipt of written approval by U.S. EPA. Unless otherwise directed by U.S. EPA and as mandated by Section 122(e)(6) of CERCIA, the Respondents shall not commence field activities until they receive written approval of the RD/RA Work Plan by U.S. EPA. Respondents shall complete the tasks outlined in the RD/RA Work Plan in accordance with the schedule outlined in the attached SOW. Failure of the Respondents to properly implement all aspects of the RD/RA Work Plan shall be deemed to be a violation of the terms of this Order.
- 5. The Site Health and Safety Plan developed pursuant to this Order shall be in accordance with U.S. EPA's guidance and protocol. After approval of the Site Health and Safety Plan by U.S. EPA Representatives, Respondents shall implement the Plan during all phases of activity at the Facility.

B. Respondents' Contractor and Remedial Design

All remedial work to be performed by the Respondents pursuant to this Administrative Order shall be under the direction and supervision of a qualified professional engineer. Prior to the initiation of remedial work at the Facility, the Respondents shall notify U.S. EPA and the WDNR, in writing, of the name, title, and qualifications of any proposed engineer to be used in carrying out the remedial work to be performed pursuant to this Administrative Order. Selection of any such engineer shall be subject to approval by U.S. EPA in consultation with WDNR.

VI.

CUALITY ASSURANCE

Respondents shall use quality assurance, quality control, and chain of custody procedures in accordance with U.S. EPA's "Interim Guidelines and

Specifications For Preparing Quality Assurance Project Plans" (QAM-005/80) and subsequent amendments. Prior to the commencement of any sampling and analysis under this Administrative Order, Respondents shall submit a Quality Assurance Project Plan ("QAPP") to U.S. EPA and WDNR that is consistent with the Scope of Work, Work Plans, and applicable guidelines. Prior to the development and submittal of a QAPP, Respondents shall attend a pre-QAPP meeting sponsored by U.S. EPA to identify all monitoring and data quality objectives. U.S. EPA, after review of Respondent's QAPP and WDNR's comments thereon, will notify the Respondents of any required modifications, conditional approval, disapproval, or approval of the QAPP. Upon notification of disapproval or any need for modifications, Respondents shall make all required modifications to the QAPP within thirty (30) calendar days of receipt of such notification.

Respondents shall ensure that U.S. EPA personnel or their authorized representatives are allowed access to any laboratory utilized by the Respondents in implementing the Order. Respondents shall ensure that any such laboratory will analyze samples submitted by U.S. EPA or WDNR for quality assurance monitoring.

VII.

FACILITY ACCESS, SAMPLING, DOCUMENT AVAILABILITY

A. To the extent that the Facility or other areas where work under this Order is to be performed is under ownership or possession by someone other than the Respondents, Respondents shall obtain all necessary access agreements. In the event that after using their best efforts Respondents are unable to obtain such agreements, Respondents shall immediately notify U.S. EPA and U.S. EPA may then, at its discretion, assist Respondents in gaining

access, to the extent of their authority and as provided by appropriate U.S. EPA guidance.

- B. Respondents shall provide access to the Facility to U.S. EPA employees, contractors, agents, and consultants, as well as to representatives of the WDNR, at all reasonable times, and shall permit such persons to be present and move freely about the area in order to conduct inspections, take samples, and to conduct other activities which U.S. EPA or WDNR determine to be necessary. Respondents shall ensure that U.S. EPA and WDNR personnel and authorized representatives are allowed to oversee all remedial activities, and are granted access to the laboratory(ies) and to the records of the laboratory(ies) utilized by the Respondents for analyses required under the Work Plan.
- C. The Respondents shall make available to U.S. EPA and the WDNR the results of all sampling and/or test or other data generated by the Respondents with respect to the implementation of this Administrative Order, and shall submit these results in monthly progress reports as described in Section IX of this Administrative Order.
- D. At the request of U.S. EPA or the WDNR, the Respondents shall allow split or duplicate samples to be taken by U.S. EPA, the WDNR and/or their authorized representatives, of any samples collected by the Respondents pursuant to the implementation of this Administrative Order. The Respondents shall notify U.S. EPA and the WDNR not less than fourteen (14) calendar days in advance of any sample collection activity. In addition, U.S. EPA and the State shall have the right to take any additional samples that U.S. EPA or the WDNR deem necessary.

PROGRESS REPORTS

- A. The Respondents shall provide to U.S. EPA and WDNR written monthly progress reports which: (1) describe the actions which have been taken toward achieving compliance with this Administrative Order during the previous month as well as such actions, data, and plans which are scheduled for the next month; (2) include all results of sampling and tests and all other data received by the Respondents during the course of the Work; (3) include all plans and procedures completed under the RD/RA Work Plan during the previous month; and (4) include sections detailing anticipated problems/recommended solutions, problems encountered/ resolved, deliverables submitted, upcoming events/activities planned, key personnel changes, and scheduling. These progress reports are to be submitted to U.S. EPA and WDNR by the tenth day of every month following the effective date of this Administrative Order.
- B. If the date for submission of any item or notification required by this Administrative Order falls upon a weekend or state or federal holiday, the time period for submission of that item or notification is extended to the next working day following the weekend or holiday.
- C. Upon the occurrence of any event during the performance of the Work which, pursuant to Section 103 of CERCIA, requires reporting to the National Response Center, Respondents shall immediately orally notify the U.S. EPA Remedial Project Manager ("RPM") and WDNR, or, in the event of unavailability of the U.S. EPA RPM, the Emergency Response Branch, U.S. EPA Region V, in addition to the reporting required by Section 103. Within fourteen (14) calendar days after the onset of such an event, Respondents shall furnish to the U.S. EPA and WDNR a written report setting forth the events which occurred and the measures taken, and to be taken, in response thereto. Within thirty

(30) calendar days after the conclusion of such an event, Respondents shall submit a report to U.S. EPA and WDNR setting forth all actions taken to respond to the event.

IX.

REMEDIAL PROJECT MANAGER/PROJECT COORDINATORS

- A. U.S. EPA will designate a Remedial Project Manger ("RPM") and WDNR will designate a Project Coordinator for the Facility, to observe and monitor the progress of any activity undertaken pursuant to this Administrative Order. The RPM shall have the authority lawfully vested in an RPM by the National Contingency Plan, 40 CFR Part 300, as amended. The Respondents shall also designate a Project Coordinator who shall have primary responsibility for implementation of the Work at the Facility.
- B. To the maximum extent possible, except as specifically provided in this Administrative Order, communications between the Respondents and U.S. EPA concerning the terms and conditions of this Administrative Order shall be made between Respondents' Project Coordinator and the RPM.
- C. Within seven (7) calendar days after the effective date of this Administrative Order, the Respondents shall provide written notice to the U.S. EPA RPM, the U.S. EPA's Office of Regional Counsel, and WDNR in writing, of the name, address and telephone number of the designated Project Coordinator and an alternate Project Coordinator.

X.

RETENTION AND AVAILABILITY OF INFORMATION

A. The Respondents shall make available to U.S. EPA and WDNR, and shall retain during the pendency of this Administrative Order, and for six years after termination of this Order, all records and documents in their

possession, custody, or control which relate to the performance of this Administrative Order, including, but not limited to, documents reflecting the results of any sampling, tests, or other data or information generated or acquired by the Respondents or on behalf of the Respondents with respect to the Facility. At the conclusion of the six year period following termination of this Order, the Respondents shall provide written notice to the U.S. EPA RPM, the U.S. EPA's Office of Regional Counsel, and WDNR, ninety (90) calendar days prior to the destruction of such documents, and upon request by U.S. EPA or WDNR, the Respondents shall relinquish custody of the documents to U.S. EPA or the WDNR.

- B. The Respondents may assert business confidentiality claims covering part or all of the information provided in connection with this Administrative Order in accordance with Section 104(e)(7)(F) of CERCIA, 42 U.S.C. Section 9604(e)(7), and pursuant to 40 CFR Section 2.203(b) and applicable State law.
- C. Information determined to be confidential by U.S. EPA will be afforded the protection specified in 40 CFR Part 2, Subpart B and, if determined to be entitled to confidential treatment under State law by WDNR, afforded protection under State law by WDNR. If no such claim accompanies the information when it is submitted to the U.S. EPA and WDNR, the public may be given access to such information without further notice to the Respondents.
- D. Information acquired or generated by the Respondents in performance of the Work that is subject to the provisions of Section 104(e)(7)(F) of CERCIA, 42 U.S.C. Section 9604(e)(7(F), shall not be claimed as confidential by the Respondents.

The Respondents are advised, pursuant to Section 106(b) of CERCIA, 42 U.S.C. Section 9606(b), that willful violation or subsequent failure or refusal to comply with this Order, or any portion thereof, may subject the Respondents to a civil penalty of no more than \$25,000 per day for each day in which such violation occurs, or such failure to comply continues. Failure to comply with this Administrative Order, or any portion thereof, without sufficient cause may also subject the Respondents to liability for punitive damages in an amount equal to three times the amount of any costs incurred by the U.S. EPA as a result of the Respondents' failure to take proper action, pursuant to Section 107(c)(3) of CERCIA, 42 U.S.C. Section 9607(c)(3).

XII.

OTHER CLAIMS

U.S. EPA and WDNR are not to be construed as parties to, and do not assume any liability for, any contract entered into by the Respondents in carrying out the activities pursuant to this Administrative Order. The proper completion of the Work under this Administrative Order is solely the responsibility of the Respondents.

XIII.

NOTICES

Whenever, under the terms of this Administrative Order, notice is required to be given, or a report or other document is required to be forwarded by one party to another, such correspondence shall be directed to the following individuals at the addresses specified below:

As to the United States or U.S. EPA; As to WDNR

a. Jeffrey A. Cahn
Assistant Regional Counsel
Attn: Hagen Farm Site

Theresa Evanson State Project Coordinator Hagen Farm Site (5CS-TUB-3)
Office Regional Counsel
U.S. Environmental Protection
Agency
230 South Dearborn Street
Chicago, Illinois 60604

Department of Natural Resources Box 7921 Madison, Wisconsin 53707

and;

b. Jae B. Lee
Remedial Project Manager
Hagen Farm Site
Remedial and Enforcement Response Branch (5HS-11)
U.S. Environmental Protection
Agency
230 South Dearborn Street
Chicago, Illinois 60604

XIV.

CONSISTENCY WITH NATIONAL CONTINGENCY PLAN

The U.S. EPA has determined that the Work, if properly performed as set forth in Section V hereof, is consistent with the provisions of the National Contingency Plan pursuant to 42 U.S.C. Section 9605.

XV.

RESERVATION OF RIGHTS

- A. Nothing contained herein shall be construed to prevent U.S. EPA from seeking legal or equitable relief to enforce the terms of this Administrative Order, or from taking the legal or equitable action it deems appropriate and necessary, or from requiring the Respondents in the future to perform additional activities pursuant to CERCIA, 42 U.S.C. Section 9601 et seq., or any other applicable law.
- B. U.S. EPA reserves its right to bring an action against Respondents pursuant to Section 107 of CERCIA, 42 U.S.C. Section 9607, for recovery of any costs incurred by U.S. EPA in connection with the Hagen Farm Facility.

MODIFICATION

Except as provided for herein, there shall be no modification of this Administrative Order without written approval of U.S. EPA.

XVII.

EFFECTIVE AND TERMINATION DATES

- A. This Administrative Order shall be effective March 15, 1991.
- B. When the Respondents determine that they have completed the Work, they shall submit to U.S. EPA and WDNR a Notification of Completion. Upon receipt of such Notification, U.S. EPA and WDNR shall schedule final inspections and close out activities as described in the June 1986 U.S. EPA Superfund Remedial Design and Remedial Action Guidance. Such activities shall include, at a minimum, the following:
 - "Prefinal Construction Conference" by U.S. EPA, WDNR and the Respondents;
 - 2) "Prefinal Inspection" by U.S. EPA and WDNR;
 - 3) Preparation of a "Prefinal Inspection Report" by the Respondents.
 - 4) "Final Inspection" by U.S. EPA, WDNR, and the Respondents.

The final remedial action report shall summarize the work performed, any modification to the RD/RA Work Plan, and the performance levels achieved. The summary shall include or reference any supporting documentation.

Upon receipt of the final remedial action report, U.S. EPA and WDNR shall review the accompanying report and any other supporting documentation and conduct any appropriate site inspection. U.S. EPA shall issue a Certification of Completion upon its determination that the Respondents have

satisfactorily completed the Work and have achieved standards of performance required under this Administrative Order for this Operable Unit.

XVIII.

ACCESS TO ADMINISTRATIVE RECORD

The Section 106 Administrative Record supporting the above Findings of Fact and Determinations is available for review on weekdays between the hours 8:00 a.m. and 5:00 p.m., at the U.S. EPA, Region V, 230 South Dearborn Street, Chicago, Illinois 60604. Please contact Jeffrey A. Cahn, Assistant Regional Counsel at 312-886-6670, for review of the Section 106 Administrative Record at this location. The 106 Administrative Record is also available for review at the Stoughton Public Library, 304 S. 4th St., Stoughton, Wisconsin 53589.

XIX.

OPPORTUNITY TO CONFER

A conference has been scheduled for March 13, 1991, 10:00 am in the northwest corner conference room on the 11th floor, U.S. EPA Region V, 230 South Dearborn Street, Chicago, Illinois. You may attend this conference to discuss with U.S. EPA this Administrative Order and its applicability to you. You may appear in person and/or by an attorney or other representative.

Any comments which you have regarding this Administrative Order, its applicability to you, the correctness of any factual determinations upon which the Order is based, the appropriateness of any action which you are ordered to undertake, or any other relevant and material issue must be reduced to writing and submitted to U.S. EPA on or before March 13, 1991. Any such writing should be directed to Jeffrey A. Cahn, at the address cited above.

Respondent shall provide notice in writing to Jeffrey A. Cahn, at the address cited above, stating its intentions to comply with the terms hereof.

Such notice shall be received by U.S. EPA on or before the effective date of this Administrative Order. In the event any Respondent fails to provide such notice, said Respondent shall be deemed not to have complied with the terms of this Administrative Order.

Respondents are hereby notified that U.S. EPA will take any action pursuant to Section 106 (a) of CERCIA, which may be necessary in the opinion of U.S. EPA for the protection of public health or welfare or the environment, and Respondents may be liable under Section 107 (a) of CERCIA, for the costs of these government actions.

IT IS SO ORDERED:

Davie A.

Director, Waste Management Division

U.S. EPA, Region V

EFFECTIVE DATE: March 15, 1991

Appendix I Record of Decision (ROD)

HAGEN FARM SITE, WI SOURCE CONTROL OPERABLE UNIT

DECLARATION FOR THE RECORD OF DECISION

Site Name and Location

Hagen Farm Site, Source Control Operable Unit Dane County, Wisconsin

Statement of Basis and Purpose

This decision document represents the selected remedial action for the Hagen Farm site, in Dane County, Wisconsin, Source Control Operable Unit, which was chosen in accordance with the Comprehensive Environmental Response, Compensation and Liability. Act of 1980 (CERCLA), as amended by the Superfund Amendments and Reauthorisation Act of 1986 (SARA) and, to the extent practicable, the Mational Oil and Hazardous Substance Pollution Contingency Plan (MCP).

This decision is based on the Administrative Record file for the Hagen Farm site.

The State of Wisconsin concurs with the selected remedy.

Assessment of the Site

Actual or threatened releases of hazardous substances from this site, if not addressed by implementing the response action selected in this Record of Decision (ROD), may present an imminent and substantial endangerment to public health, welfare, or the environment.

Description of Remedy

This source control operable unit is the first of two operable units for the site. The selected remedial action for this operable unit addresses the source of contamination by remediation of on-site wastes and contaminated sub-surface soils.

The major components of the selected remedy include:

- * Within the larger area of contamination (AOC), consolidation of non-native materials from disposal areas B and C into disposal area A with subsequent backfilling of disposal areas B and C with clean soil material;
- * Installation of a WDNR NR 504 solid waste cap over disposal area A after consolidation;

RECORD OF DECISION

DECISION SURPLY

HAGEN FARM SITE

SOURCE CONTROL OPERABLE UNIT

. DANE COUNTY, WISCONSIN

Prepared By:

U.S. Environmental Protection Agency

Region V

Chicago, Illinois

September, 1990

BOD SUMPRY BROWN FARM SUPERFUND SITE, SCHOOL CHEMELE UNIT DING COUNTY, WINCHEDE

SITE LOCATION AND DESCRIPTION

The Hagen Farm Site (the "Site") is located at 2318 County Righmay A, approximately one mile east of the City of Stoughton, Dane County, Wisconsin. The 10-acre Site is situated in a rural surrounding that is downated largely by sand and gravel mining and agriculture. Soil and gravel mining operations are located northwest, northeast and south of the Site. The Stoughton Airfield is located adjacent to the northwest corner of the Site. County Highway "A" passes just south of the Site (See Figure 1).

The City of Stoughton's municipal wells are located approximately two miles to the west, and eight private wells are located within 1,200 feet of the Site. The private wells located at the Site are no longer in use. Approximately 350 people reside within one mile of the Site.

The Site is located in the Yahara River watershed, in an area of flat to gently rolling topography. The Yahara River is located approximately 1.5 miles to the West and flows in a southerly direction. The land surface generally slopes toward the Yahara River from topographically high areas located to the northeast and east. Surface water drainage in the area is generally poorly developed, apparently due to permeable surface soils. The only substantial surface water bodies in the area are a pond locate approximately 1/2 mile south of the Site and the Yahara River. There is no designated Wisconsin State significant habitat, or historic landmark site directly or potentially affected. There are no endangered species within close proximity of the Site.

The Site is located in an area dominated by glacial outwash deposits, which extend approximately one-half mile to the northeast. These deposits are dominated by sand and gravel. Beyond this, ground moraine and occasional drumlins are encountered. Incustrine deposits associated with Glacial lake Yahara are located approximately one-eighth mile south. Bedrock, primarily sandstones and dolomites, underlie the glacial deposits in this area. Bedrock generally slopes from the west to southwest, toward a preglacial valley associated with the Yahara River. The depth to bedrock ranges from 50 to 80 feet near the Site.

The current Site topography is the result of sand and gravel mining and waste disposal activities. Prior to these activities, the ground surface probably sloped from the existing topographically high area located west and northwest toward the southeast and east. The excevated area in the northwest corner of the property is flat. This flat area is separated by a ridge from the water-filled depression located to the northeast.

Within the Site's larger "Area of Contamination (AOC)", waste disposal took place within three subareas. These subareas are A (6 acres, located in the

seeding civil demagns for reduced property values and potential health hearths resulting from groundester and well contamination. The State of Miscorsin obtained a dismissal of its 1963 enforcement action spainst was and Universal after the Site was listed on the National Rejorities List (MMLP). In 1986, the parties to civil litigation brought by the nearby residents to the Site against WSU and Universal resched a settlement. In exact terms of the settlement were confidential. It is known, however, that one of the terms of the settlement required WSU to purchase the Site property from Occin Repen, as well as other property located adjacent to the Site. Upon acquiring these properties, WSU resed the structures constructed thereon. residents at the Site brought a civil action against NSG and Universal SA Sits į

The site was proposed for inclusion on the NFL on September 18, 1985. The Site was placed on the NFL in July of 1987. Stranguartly, NSHL and Universal, the two potentially responsible parties ("FRES") named by U.S. EMA in correction with the Site to date, entered into an Administrative Order by Consent (U.S. EMA Docket No. W 87-C-016, dated September 14, 1987) (the "Consent Order") with the U.S. EMA and the NURL. In the Consent Order, West and Universal agreed to conduct a Remedial Investigation and Peachbility Study ("NU/IS") at the Site. Accordingly, in July of 1988, upon U.S. EMA approval, in consultation with the NURL, of the required Nuck Flans, fieldwork at the Site commenced.

Two operable units, which are being conducted concurrently, have been defined for the Site. Operable Unit ("OU") I, which is the Source Control Operable Unit ("SCUU"), is intended to address waste refuse and sub-surface soils ("Waste/sub-Soils") at disposal area A and the two smaller disposal areas B and C. OU II, which is the Groundwater Control Operable Unit ("GCUU"), is intended to address the contaminated groundwater at the Site. The OU approach was agreed upon after discussions among U.S. EPA, WDNR, and FROW during the early phase of the implementation of the Work Plan for the Ä

The RI for the SCUI was completed in early 1989, and the Technical Memorandum for the SCUI was submitted in March 1989. The RI for the GCUI was initiated in July 1989 and the Technical Memorandum for GCUI was submitted in February 1990. Currently, additional field activities to define the extent of plume migration are orgaing. The RI report for the GCUI, including the Endangement Assessment, is scheduled for completion in July 1991. The ROD for the GCUI is scheduled for early 1992.

COMMUNITY RELATIONS ACTIVITIES

A Community Relations Flan for the Site was finalized in July 1988. This document lists contacts and interested parties throughout the local and government community. It also establishes communication pathways to ensure timely dissemination of partinent information. The RI/FS and the Proposed Flan for the SCOU were released to the public in July 1990. All of these the Stoughton Public Library and Klongland Realty. An administrative record file containing these documents and other site-related documents was documents were made available in the information repositories maintained at

source of groundanter contamination. The VOCs in the Waste/sub-Soils are considered to be the principal threat for this SCOU.

The groundwater contamination problem will be addressed in a future GCCV, Record of Decision which is expected to be the final action for the Site.

The FS identified two remedial objectives for the SCOU based on the data obtained during the RI and the possible exposure routes identified. The objectives identified in the FS are:

- 1) To reduce or minimize direct contact with contaminated waste and soils; and,
- 2) To reduce or minimize release of contaminants to the groundater.

V SIMORY OF SITE CHARACTERISTICS

()

In March, 1969, a Technical Manorandum for the SCOU was completed under the quidence and oversight of U.S. EFA and WDNR. The Remedial Investigation (i.e., Technical Manorandum #1) for the SCOU was to determine the nature and extent of contamination at the source, and evaluate possible exposure pathways. The report summarized all soil-gas, test-pit, soil, air, and on-site groundwater analytical data that had been collected. This report should be consulted for a more through description of the site characteristics.

The following are the results of RI at the Site:

- Based on the geophysical survey, soil-gas, and test-pit survey, it appears that most of the waste disposal activity occurred in disposal area A. Disposal area A encompasses approximately six acres (100 feet long and 400 feet wide). The wastes within disposal area A are buried to a depth of two to three feet near the eastern edge, to a depth of 16 feet near the center. Eight feet is the average overall thickness of buried wastes. The volume of waste for disposal area A is estimated at 67,650 cubic yards. The test-pit survey and refuse borings indicate that the type of waste present in disposal area A includes plastic sheeting, paper-coated plastic, paint sludge, grease, rubber, and municipal waste, such as wood, glass, paper, and scrap metal. No drums were discovered during the test-pit excavation activity.

Based upon refuse borings, test-pits, and groundwater table measurements, the bottom of the wastë refuse material is estimated to be 10 to 15 feet above the seasonal high water table in disposal area A. The volume of unsaturated sub-waste soils for disposal area A is approximately 112,000 cubic yards.

Disposal areas B and C seem to contain only scattered domestic wastes. A geophysical survey, test-pits and soil gas tests revealed a small quantity of municipal waste in disposal areas B and C. It appears that disposal areas B and C were not used for the disposal of industrial

system. Furthermore, based on surface water quality results and inferred groundwater flow paths, it appears the drainage ditch east of the Site and Surby's pond to the south are not groundwater discharge points.

The results of the RI at the Site indicate that the wests refuse materials in disposal area A have been and continue to be a source for sub-surface soil and groundwater contamination.

The investigation for the groundater contamination at the Site is expected to be completed by the end of 1990. Initial results of the investigation indicate that the groundater flows to the south and that the contaminant plume extends south of the pond located one-half mile from the Site. The exact boundary of the southern edge of the plume has not yet been determined. Seven residential wells located downgradient of the Site were sampled on August 1990 for any potential impact from the contaminant plume. More details of the nature and extent of the groundanter contaminant plume will be addressed in the subsequent GOO.

VI SIMARY OF SITE RISKS

()

This section qualitatively describes the risks posed by contaminants in Waste/sub-Soils to human health and the environment. Based on the historical findings and on-site groundwater data, which exceeded the drinking water and groundwater quality standards of the U.S. EPA and the WINR, respectively, it is determined that remedial action is needed to address the source of the groundwater contamination. Because this remedy is a source control operable unit, a final baseline risk assessment for the Site is not available. No quantitative risk numbers have been calculated for exposure to site contaminants. However, qualitative risk information is organized and outlined below to demonstrate that action is necessary to stabilize the site and prevent the degradation of the groundwater. The baseline risk assessment for the Site will be conducted later during the GCCU phase.

The greatest risk present at the Site is from the groundwater contamination. However, the source of the groundwater contamination is the contamination found in the Waste/sub-Soils at the Site.

The following is a qualitative discussion of the site risks.

(A) Contaminants of Concern

The following chemicals have been detected in soil gas, leachate and consite groundwater wells at concentrations above bedground, and screened waste refuse analyses and can be inferred to be present in source wastes.

VOC3

Semi-VOCs

- . Ethylbenzene
- . Benzyl alcohol
- . bis (2-chloroisppropyl)ether

- . Toluene
- . Phenol

. bis (2-ethylhexyl)phthalate

Waste/sub-Soils to the groundwater. Present risks from the groundwater are unacceptable. As shown in Table 3, the contaminants in the on-Site groundwater exceed Pederal and State Standards. Continued leaching of contaminants from the Waste/sub-Soils to the groundwater will result in continued unacceptable risks. Should the contaminants migrate to existing private wells, or in the unlikely event of future site development involving the installation of a water supply well, contaminant exposure via groundwater use and consumption may occur. Hore detailed evaluation of both current and future potential human health and environment risks associated with contaminated groundwater exposure will be addressed in subsequent steps of GCOU.

Implementation of the selected remedy as presented by this SCOU will reduce exposure to contaminated soils, control air emissions, and minimize or reduce contaminant migration to the groundater.

(C) Environmental Assessment

()

The natural habitat existing prior to sand and gravel mining operations at the Site was destroyed. At present, the waste disposal area is covered with a layer of soil material which supports vegetation primarily consisting of grasses and other harbaceous plants, with some tall trees. This area is likely frequented by wildlife including birds, small mammals and deer. Although an inventory of plant and animal species has not been performed, the Site is not known to be inhabited by rare or endangered species. I and in the vicinity has been developed for agricultural, mining and commercial purposes. Sensitive ecological habitats (e.g., wetlands) are not in close proximity to the Site. The Site is not in a floodplain. The potential adverse impacts of Site wastes on the surrounding ecology are not considered appreciable in comparison to the loss of habitat which historically occurred during the active sand and gravel mining phase of the Site.

VII DOCUMENTATION OF SIGNIFICANT CHANGES

No significant changes have been made since the publication of the FS and Proposed Plan in July 1990.

VIII DESCRIPTION OF ALTERNATIVES

Alternatives for the remediation of contaminated Waste/sub-Soils, were developed to achieve the following goals:

- minimize the potential for direct contact with the contamination;
- minimize the potential for migration of waste/sub-Soils contaminants into the groundwater.

A comprehensive list of appropriate remedial technologies was identified for Source Control. These technologies were screened based on their cost,

not involve any treatment to reduce the mobility, toxicity, or volume of waste, it was determined that the more impermeable capping option afforded by Subtitle C and MR 181 was both relevant and appropriate under this alternative. Therefore, only the Subtitle C cap will be evaluated for this alternative during the comparative analyses. No treatment of contaminants is involved in this alternative.

The cap would be designed to cover disposal area A. The area to be capped is approximately 240,000 eq ft (5.5 acres). The capital costs of this alternative is approximately \$2,751,000, and arrowal Operation and Maintenance (OSA) cost is \$8,899. The 30-year Present Worth (FW) cost is \$2,888,000. The amount of time necessary to implement this alternative would be 7 months.

ADDEROUVE 3: IN-SITU VARIR EXTRACTION AND CAPPING

In this alternative, the Waste/sub-Soils in disposal area A would be treated using In-Situ Vapor Extraction (ISVE). Gas is extracted from the Waste/sub-Soils through extraction wells placed strategically at the Site. The gas travels from the wells through header pipes using a blower. The off-gases would be treated and discharged to the atmosphere.

Vapor extraction is used primarily for treating VOC contamination. A vapor extraction system is relatively inexpensive and allows for process flexibility during remediation activities. The major costs for this technology are the installation of extraction and injection wells. The number of wells used may vary during operation to improve system efficiency. By treating the Waste/sub-Soils in place without excavation, release of untreated contaminants to the atmosphere is avoided.

Prior to the implementation of in-Situ Vapor Extraction, non-native materials from disposal areas B and C will be consolidated to disposal area A. Approximately 37,000 cubic yards of fill is needed to bring area A up to required slopes before cap placement. Consolidation of solid waste materials from areas B and C will provide some of the required fill material and will ensure that all site waste materials are properly confined. Then a low permeability cap, which meets the requirements of NR 504.07, WAC, will be installed over disposal area A (see Figure 5). The NR 504.07 cap would reduce leachate production by reducing infiltration and would control moisture content in the Waste/sub-Soils to improve the Vapor Extraction system performance.

As stated for Alternative 2, a RCRA Subtitle C cap would be potentially relevant and appropriate. The U.S. EPA and MDRR have determined that for this particular Alternative, the Subtitle C cap, while relevant, is not appropriate because construction of the ISVE system would impair the integrity of a Subtitle C cap. An NR 504.07 cap will provide an adequate level of protection when combined with treatment and can easily be repaired after installation of the ISVE system.

For the discharge of off-gas emitted from the Vapor Extraction procedure,

()

would be constructed within a minimally contaminated area of the ACC. The double lined treatment/disposal cell would provide maximum protection for treatment of the contaminants. After completion of treatment, a RCFA Subtitle C (NR 181, NRC) cap would be placed over the treatment/disposal unit. The Subtitle C cap would be relevant and appropriate because the integrity of the cap could be maintained and it would provide maximum protection to the treatment/disposal unit. The LTR requirements are not ANNER for this alternative, because no "placement" of waste occurs. Upgrading an existing landfill facility to consolidate wastes within the ACC does not constitute placement, according to the NCP.

For the discharge of excess leachate produced from this alternative, the NR 105, NAC, Surface Natur Quality for Toxic Substances, is an ANAR. The excess leachate would be treated in order to meet NR 105 standards. A toxicity characteristics leaching procedure ("TCLP") test will be conducted for the treatment sludge to determine whether further treatment is necessary for disposal in a RCRA compliant landfill in order to comply with land Disposal Restrictions ("LIRS").

The volume of waste to be consolidated and treated is approximately 67,650 cubic years from disposal area A and non-native materials from disposal areas B and C. The capital costs of this alternative is approximately \$12,894,000. The average annual OEM cost is \$82,300, and the 30-year FM cost is approximately \$14,129,000. The amount of time necessary to implement this alternative would be 10 years.

ALTERNATIVE 5: WASTE EXCAVATION WITH ON-SITE INCINERATION. VAROR EXTRACTION AND CAPPING

This alternative incorporates waste excavation with on-site incineration and disposal. The excavation activities are the same as described in Alternative 4. On-Site materials handling, staging, and storage may also be required. Waste would be characterized prior to incineration. Treatment residuals, such as ash and scrubber water, would be further treated, if necessary, and disposed of off-Site in accordance with the IIRs.

Under this alternative, a large depression would be created by waste excavation exposing contaminated sub-surface soils in disposal area A. This depression would be filled with imported clean fill materials and the non-native materials from disposal areas B and C, followed by a Solid Waste cap. The contaminated sub-surface soils would be treated with ISVE.

For this alternative, incineration would be done in an incinerator which meets the design requirements of 40 CFR Part 264 Subpart O. A TCLP test will be conducted for the treatment residuals, such as ash and scrubber water, to determine whether further treatment is necessary for disposal in a RCRA compliant landfill in order to comply with LIRs requirement.

The volume of waste to be incinerated is approximately 67,650 cubic yards from disposal area λ . The capital costs of this alternative is

necessary to implement these alternatives.

For Alberrative 2, a RCWA Sattitle C multi-layer cap would be installed in order to comply with RCWA cap design standards.

(i.e., NR 504.07, NAC). Alternative 4 would meet State (NR 181, NAC) : Pederal (40 CFR 264.301) bezardous waste landfill requirements. Alternative 4 also would meet the Pederal RCNA Subtitle C cap requirem Alternatives 3 and 5 would meet the State landfill closure requires /4 ... we sould? NOC). Alternative 4 would meet State (NR 181, NR R

E 5. F 45, Centrol of Hazardous Pollutants, is an AMMR for Alternatives 3, 4 The extracted off-gases should be treated in order to meet NR 445 n limit requirements.

Turic Statuscas Central Act ("ISCA") is not an ANNR for this site because the detected at the Site, at a maximum level of 300 ppb, is less than 5

The still listing of ANNE for the Site is contained in the 75.

3. Icro-Term Effectiveness and Bermanapor

Residual risks associated with direct contact with westes will be reduced by each alternative through capping, which will minimize direct exposure tweates. Alternatives 3, 4 and 5 will reduce these risks further by removing and treating, biodegrading or incinerating contaminants. Risks associated with direct contact with weste materials in the future will be minimized through implementation of institutional controls. g

Residual risks associated with migration of contaminants from the source to groundwater were considered greatest for Alternative 2, because the wastes are only contained and not treated or destroyed. Alternatives 3 through 5 provide the lowest residual risks to groundwater since the source of groundwater contamination is being treated.

Effectiveness is exclusively dependent on maintaining the integrity of the cap over the long term for Alternative 2. Alternative 2 will not remove contaminants within the waste which could ultimately migrate to the groundwater. Therefore, maintenance of the cap is key to the long-term effectiveness and permanence of this alternative.

Alternative 2 through 4 will be effective in achieving remedial objectives through installation of multi-layer cap, which will limit the infiltration of precipitation through the landfill and preclude the leaching of contaminants into the groundwater.

through vapor extraction. In addition, the installation of the solicap will minimize the leaching of contaminants into the groundwater. Alternative 3 will be effective in removing VCCs in the Waste/sub-Soils through vapor extraction. In addition, the installation of the solid waste

(

objectives through biological degradation. Alternative 4 is anticipated to be effective in achieving remedial Tests at other sites have

1

8 However, the levels of potential contaminant exposure to remunctions could be minimized by the use of personal protective standard dust control measures in each alternative. Alternative architectard to pose minimal risks to remadiation workers community because they do not involve excevating the veste. S sprin Alternative 5, Weste Econvation with on-site Incineration, may pose risks to the surrounding ecology were not alternative g community and workers due to increased air emissions. considered Alternatives 2 and 3 appraciable for any of diation. Additional 品品

6. Implementability

Alternatives 2 is the essiset to technically implement compared to the other three alternatives. Alternative 3 is somethat easier to implement than Alternative 4 and 5 because it involves less construction at the The most difficult alternative to implement would be Alternative 5. Difficulties associated with this alternative include accessing a pocidination with relevant agencies. suplementary that source on-site, disposing of the ash, supplying sufficient water needed for the scrubbers, and treating and disposing the contaminated scrubber water. Alternatives 3 and 4 would both be relatively straightforward to implement technically. Administratively, alternatives 2 and 3 are easier than alternatives 4 and 5 because they involve less Site

Alternatives 2 through 4 require services and material available. It is assumed that appropriate material construction could be obtained from a borrow source miles of the Site. For Alternative 5, materials are elternatives. evailable, but their availability is more restricted than the other a borrow source located within 5, materials and services are s and meterials that should de persona cap H g

7. Out

Maintenance \$2,888,000. Alternative 2 involves a capital costs of \$2,751,000, armal operation and (OGM) costs of \$8,899 and a 30-year Present Worth (FM) cost of and a 30-year Present Worth

Alternative 3 involves cost of \$29,530, and a a capital costs 30-year FW cost 22 \$2,679,400, Average arrival OSH

Alternative 4 involves cost of \$82,300, and a a capital costs 30-year FW cost 22 \$12,894,000, SETANE MENO TERLETA

Alternative 5 involves cost of \$22,800, and a a capital costs 30-year PH 8 22 \$59,410,000, SECTAND May Tenura

8. State Acceptance

recommendations presented The State of Wisconsin is concurs with the selected in agreement in the RI/FS alternative ement with the U.S. EPA's analyses and and the proposed plan. (presented in Section X, below). The State

regenerated, thus they are not subject to LIRs.

* Institutional controls would be relied upon to provide additional effectiveness to the remedy. These include zoning restriction, deed notice, and construction of a fence.

XI SPATUTORY DETERMINATIONS

The selected remedy must satisfy the requirements of Section 121 of CERCIA to:

- a. protect human health and environment;
- b. comply with ARARs;
- c. Be cost-effective;
- d. Utilize permanent solutions and alternate treatment technologies to the maximum extent practicable; and,
- Satisfy the preference for treatment as a principle element of the remedy or document in the ROD why the preference for treatment was not satisfied.

The implementation of Alternative 3 at the Site satisfies the requirements of CERCIA as detailed below:

a. Protection of Haman Health and the Environment

Implementation of the selected alternative will reduce and control potential risks to human health posed by exposure to contaminated waste and air emission by treating contaminated Waste/sub-Soils.

Capping the landfill, in addition to reducing any potential risks posed by direct exposure to contaminated waste, will reduce the infiltration of precipitation through the landfill. Groundwater contaminant loading will thus be reduced. In-Situ Vapor Extraction of the contaminated Waste/sub-Soils will also reduce the groundwater contaminant loading.

No unacceptable short-term risks will be caused by implementation of the remedy. The site workers may be exposed to noise and dust nuisances during construction of the cap. ISVE should not present short-term risks due to VOC emission if properly designed and monitored. A Standard Safety program will manage any short-term risks. Dust control measures and off-gas treatment would reduce those risks as well.

b. Compliance with ARARs

An NR 504.07 Solid Waste cap is an ARAR for Alternative 3. A RCRA Subtitle C cap, while relevant, is not appropriate, as described in Section VIII of this RCD. NR 445, WAC, Control of Hazardous Pollutants, is an ARAR for the discharge of off-gas from the vapor extraction procedure.

Compliance with Wisconsin Statute, Chapter 160 and NR 140, WAC, will be achieved through the selection of the final remedy for the GCCU for this


is therefore determined to be the most appropriate solution for the contaminated Waste/Sub-Soils at the Hagen Fami site.

The State of Wisconsin is in concurrence with the selected remedy. A public comment was received concerning the cost of the remedy, and this comment is fully addressed in the Responsiveness Summary.

e. Preference for treatment as a principal element

The groundester contaminant plume will be addressed in a second operable unit. Because the selected alternative treats the VOCs, which are the continuing source of groundester contamination, it will address the principal threat for the SCOU at the Site through treatment and satisfies the preference for treatment as a principal element. In addition, during full-scale implementation of ISVE, enhanced biological treatment of semi-VOCs will be investigated and if feasible, implemented as part of this remedy.


Figure 2
Site Diagram
Hagen Farm Site
Dunkirk Township, Wisconsin
(Bot To Scale)





-712EZ 4

SPECIFICATION OF HR SOLOT SOLD WASTE CAP



WASTE (0'-16')

** THE COVER LAYER WAS SPECIFIED AT 30 IN. AS A WORST CASE SCENARIO TO ADDRESS THE CONCERNS OF NR 504.07 (5).

SCALE: 1" =

THE 1

O

Groundwater Quality Summary VOCs and Semi-VOCs at Source Characterization Wells Hagen Farm FS

. Concentrations (ug/L)

	<u> Maximum</u>	Average(1)	Mo. Wells With Detection(2)
YOCs			•
2-Butanone	4,400,000	.2,620	3
Toluene	· 20	20	1
Ethylbenzene	2,400	99	3
Xylenes	35,000	1,066	5
Tetrahydrofuran	630,000	5,695	5
Seni-YOCs	·		••
Benzoic Acid	29,000	780 .	2
2.4-Dimethylphenol	330	153	2
4-Hethylphenol	6,100	243	2
Phenol	5,600	3,816	1
1,4-Dichlorobenzene	10	10	1
Benzyl Alcohol	26	26	1
Bis(2-Chloroisopropyl)Ether	19	19	1
Naphtalene _	8	8	1
4-Chloro-3-Methylphenol	7	7	1
Diethylphthalate	5	4.5	. 1
Bis(2-Ethylhexyl)Phthalate	34	18	3
Di-n-Octyl Phthalate	. 5	5	1

<u>Notes</u>

- (1) Geometric averages for positive detects at each well are calculated for duplicate analysis and multiple rounds, where applicable. Geometric average were then calculated using one single or, where more than one sample was obtained from a given well, average value for each well (5 wells).
- (2) Out of five wells. Some wells had more than one sample analyzed as indicated in (1).

TABLE 2 (Continued)

	Concent			
Compound	-Geometric Hean	Meximum	Number of(1) Samples	
Pesticide/PCB's (ug/kg)				
. Dieldrin	11.6	11.6	1	
-4,4'-DOE	18.2	18.2	1	
4,4*-000	11.9	128	4	
4,4'-001	19.2	19.2	1	
PCB-1242	104.8	284	4	
PCB-1248	338	338	1	
PCB-1254	222	222	. 1	

<u>Notes</u>

- (1) Out of 10 total sampling locations (Test Pits RSO1 to RS10), excluding RSO8 duplicate.
- (2) Sum of tentatively identified compounds.

0

Indicates concentration is below method quantitation limit. Value is estimated.

HAGEN FARM SITE SOURCE CONTROL OPERABLE UNIT DANE COUNTY, WISCONSIN

FURPOSE

()

This responsiveness summary, required by the Superfund Law, provides a summary of citizen's comments and concerns identified and received during the public comment period, and U.S. EPA's responses to those comments and concerns. All comments received by U.S. EPA during the public comment period will be considered in the selection of the remedial alternative for the Site. The responsiveness summary serves two purposes: It provides U.S. EPA with information about community preferences and concerns regarding the remedial alternatives, and it shows members of the community how their comments were incorporated into the decision-making process.

This document summarizes one written comment received during the public comment period of July 11 to August 10, 1990. The public meeting was held at 7:00 p.m. on August 2, 1990 at Dunkirk Town Hall, Stoughton, Wisconsin. No comments were submitted during the public meeting.

OVERVIEW

The preferred alternative for the Hagen Farm site was announced to the public just prior to the beginning of the public comment period. The preferred alternative includes:

- * Installation of a WDNR required NR 504 solid waste cap over disposal area A after consolidation;
- * In-Situ Vapor Extraction of the waste refuse and subsurface soils in disposal area A;
- * Off-gas treatment through carbon adsorption.

PUBLIC COMMENT AND AGENCY RESPONSE

COMMENT: It is unwise to spend more than \$2 million of the taxpayers' money to remediate the Hagen Farm site which will not affect anyone. The money should be spent to control cigarette smoking which kills thousands of people each year." In addition, the commentor stated U.S. EPA should be active in alleviating "drunk drivers."

<u>RESPONSE:</u> It is believed that the wastes in the Hagen Farm landfill have been contaminating the groundwater at the site. If the Agency does not remediate this contaminated landfill now, the landfill would contaminate the groundwater continuously in the future, and people who use this groundwater as their drinking

FINAL

ANGINITALITY MICHE THE SHIP PAR SITE STREET, STREETH

()

- 1111	21625	2475	. SIDLE	-AFFINE	200171887	SOCREERT TIPE	- SOCEREE
	×	STRUM	Setter ser Consests on Site Brainstion Seport, Sechnical Outhplan, and \$177	9.Selleti, MIR	2.3edettiste,1824 of Al	Sozzaspeoleoce .	1
· .	22	81/16/23 . <u>.</u>	Setter formerling semponess to the Segen Form Site EL/75 GAT, with the Chloride and Sulfate Analysis by Sea Chrosatography	A.Sciint,Succes Suc.	J.Bellsses,Verzys Bogr.	Coccuspositoses	.
	<i>:</i>	•	Better ser Bespesses and Berisless to Gonzots from BSIN- Begins T (A Office on the Bages fars B1/75 (AI)	i.beries,1231 et El,lec.	\$.\$71 rester,63272	Coccespedieses •	3
)	S	88/88/11	Setter per Sisterity of Setector Response for Chloride and Solfate Analyses	6.Asbergil.Tesft, Terrya Esgisceriog,Zoc.	Charg-Sta Saci, Mi, SSENI	Cozzespoolesce	•
: 	J	88/89/86 `	Setter zer Sethodology Sodifications for Sulfate and Chloride Analyses	C.Labery, Terrys Bogisecrisg, loc.	1.3ee,8001 :	Correspondence :-	\$
	7	88/30/25	Setzer re: Bork Plaz Affendes for Source Characterization	J.Dorles, Taste Syst. of El, loc.	3.3ee,8221	Estrespesience	6
<u>ن</u> '	2	84/11/14	Elift fill Sign-off Sheet	J. Bereicz, MIL of SI, Inc.	5.Lm,98271 :	Correspondence	7
, L	37	81/81/38	Setter ser Bosh Plan Microfin for Phase 2 Site Investigation and Source Control Operable Bait 25	S.Labery, Farrys Bogiovering, Inc.	J.Sec, 982 24	Cozzespoolenee	•
ا بد		81/81/25 :	Setter re: Response to Connects - Tech Seno 1	f.livery, farrys Segioceries, loc.	J.Jeries, TIDL of El, lac.	Carrespondence	•



State of Wisconsin \ DEPARTMENT OF NATURAL RESOURCES

R TELETAX NO. 006-367-367 TDO NO. 008-367-008 SOLED WASTE TELETAX NO. 808-267-278

September 6, 1990

IN REPLY REFER TO: -4440

Hr. Valdas V. Adamkus, Regional Administrator U.S. Environmental Protection Agency 230 S. Dearborn Street Chicago, IL 60604

O: MMD CC: RF FREEMAN

SUBJECT: Selected Superfund Remedy

Hagen Farm Site

Dunkirk Township, Dane County, WI

Dear Mr. Adamkus:

The Department is providing you with this letter to document our position on the proposed source control operable unit for the Hagen Farm Site. The proposal, as identified in the draft Record of Decision, includes the following:

Alternative 3:

In-Situ Vapor Extraction and Capping

Non-native waste materials from disposal areas B and C would be consolidated to disposal area A. The waste and contaminated sub-soil materials in disposal area A would be treated using In-Situ Vapor Extraction (ISVE). A low permeability cap-meeting the Wisconsin requirements for capping municipal landfills will be placed over disposal area A.

Estimated Costs: Construction - \$2,679,400 Operation and Maintenance - \$29,530 30 Year Present Worth - \$3,299,000

The total 30 year present net worth for the Hagen Farm Source Control Operable Unit is approximately \$3,299,000. The Department concurs with Alternative 3, as described in the Record of Decision for this operable unit.

RECEIVED

SEP 1 2 1990

ANGELERALITY RECORD TENED BACKE PARK STORY:

_ - 211	Ma	3132	gini :	attou		881171887		SOCRETES SEES	MCHBII
·	•	- :.	gor the Assipute for - Secretions Substances List Volatile Organic Composade in his Samples by OCINE	eerisel by	BREPA .	· •	•	•	-
	211		Separt on the Electro- sopertie and Separtie Survey Conducted at the Super Para Site	Sroon Appl	Sed Technology	Sersyn Serionering,	,lac.	Seperts/Stolles	22 .
	9	81/19/23	Prelicioery Scalth Assessment for Suger Para Site Sugerton, El	Serese of	of Bealth, i Consenty Frerenties	arme		Seperts/Stalles	23
1	227		EI/FS Bages Para Site Tocholes! Beoeresdes Booker 1 - Barch 1989	Seraye Beg	ioceriog,loc.	Coste Spot. El,loc.	et	Seperts/Stolles	26
<u>~</u>	87	esmni	Ei/IS Enges Form Site Sectories Environtes Seater 1 "	Baraya Bag	iocezi og, Ioc.	Seste Syst. 81,1se.	ef	Seperts/Stolies	25
	•	swin	Progress Report Roges Pars Superfesi Rite	83371	•	•		Begorts/Stalies	26
<u>.</u> .	45		Alternatives Array Second Secret Control Operable Sait 21/73 Segen Farm Site	Bersys Rog	ineezing,loc.		:	Beports/Stalies	27
_	224	90/02/00	22/77 Bages Fore Site feebales? Besoresden Subter 2	Bassye Bag	iscerisg, l ne.	Caste Syst. El,loc.	et ·	Beports/Stalies	21

Appendix II Administrative Record Index

FINAL

ANCISITATIVE SECON EDUCA SARES PARA ESTRE STORESTON, ESTREMENTS

Ó

्रायः श	ER MAR	. 2008	-: 3 7700	ADELPIERT	30038337 5773	-Mann
***	-ARU/U	Letter re: Courts on lite Breisstine Seport, Tocksical Ourlying, and fill?	J.Belleti,Will	_2.9esettista, tusi el 23	Eszespedeses •	• 1
#		Letter forverting responses to the Sopes Term Site 21/75 927, with the Chieride and Selfate Analysis by Lon Chronstography	4.Selin, Sweet Luc.	d.Bellson, Gersyo doge.	C erru pudese r	2
.	* . .	Letter se: Bespenses and Berisless to Comesta free BMPA- Region T & Office on the Bayes fare BITTS &MP	i.beda,Wi el U,lec.	8.87/mster,888/1	Correspondence •	•
	81/11/ 31	Better ser Bisearity of Setector Besponse for Chloride and Sulface Analyses	C. Labergil. Tealt., Terrya Bagiateriog, Loc.	Charg-Per Test, PhD, 83375	Correspondence	4
3	stware ,	Setter ze: Bethodology Bodifications for Balfate and Chloride Analyses	C.Labery, Verzya Boglaceriog, Inc.	3.1ee,8000 	Estempolenee :-	s
2	81/10/25	Setter ser Bost Flan Affendes for Source Characterisation	d.Bordes, twice Syst. of El, loc.	J.See, MIPL	Eostespeolesee	•
.	81/11/11	EI/TS QUIP Sign-off Sheet	J. Series, MIL of II, Lat.	J.Sec,88824 :	Carrespondence	7
20	85/67/29	Setter so: Fost Flan Métades for Phase 2 Site Investigation and Source Control Operable Buit 28	6.Lebery, Serrys Socionering, Inc.	J.Sec, 19992	Cozzespoolesee	a .
3	65/61/75	Setter se: Besponse to Consents - Tech Beso 1	Bogincering, Inc.	i.lerder,TIM of Ci,ist.	forrespondence	9

ı

- ANGILIATELATITI ESCOLO 20061 - BLASTO PLANO 2007 (*) - 200602001, ESCOLOSSE

Sales after the training

the continue of the

e mes ma	2711 :	atrou :i	880171387	SOCREET SIN	-80CHTH11
_	for the facilitie for ferentees februares List Veletile Organic Congessis in Air Surples by Ot/ES			•	
218 80/89/NI	Supert on the Electro- supertie and Eugentic Survey Conducted at the Suger Para Site	From Applied Technology	Serzys · Septemering, lac.	Seports/Stolles	
9 60/89/23	Freifeisery Scalth Assessment for Bogen Farn Site Stooghton, EI	SDES, Dir. of Bealth, i Berese of Consulty Bealth and Provention	A2300	Seperts/Stelles	21
227 83/83/14	EL/75 Engen Farm Site Technical Beneranden Benjer 1 - Barch 1989	Serrys Begiocering, loc.	Beste Syst. of EL,loc.	Seports/Stolles	×
87 83/83/8 i	EL/FE Sopen Fare Site Fechaleal Seasonates Seaber 1	Surrys Bogioecting, Inc.	Saste Sgat. of El,loc.	Aqusta/Stolics	25
i souries	Stoftess Report Rojes Fara Superfaul Site			logerts/Stalles	26
wanen w	Alternatives Array Soccaest Source Control Operable Sait 21/78	Serzys Bogiseering, Inc.		Sepera/Stalles	27
	Sign for Site Si/It Sign for Site fechalcal Sentanta States 2	Corage Degleeering, Inc.	Carte Spit. of El,loc.	Seperts/Station	21

Appendix III Scope of Work (SOW)

Scope Of Work For The Remedial Design and Remedial Action Work Plan at the Hagen Farm Site, Dane County, Wisconsin

I. PURPOSE

The purpose of the Scope of Work ("SOW") is to implement the Hagen Farm site, Source Control Operable Unit, Record of Decision ("ROD") which the United States Environmental Protection Agency ("U.S. EPA") issued in September 1990 to select a source control remedial action for the Hagen Farm Superfund site. In designing and implementing the remedial action at the Hagen Farm site, the Respondents shall follow this SOW, the U.S. EPA Superfund Remedial Design and Remedial Action Guidance, the ROD, the approved Remedial Design ("RD") and Remedial Action ("RA") (sometimes referred to together as "RD/RA") Work Plans, any additional guidance provided by U.S. EPA, and the provisions of the Administrative Order.

II. DESCRIPTION OF THE REMEDIAL ACTION

The Hagen Farm site (the "Site") consists of three disposal areas. In general, the remedial action which the Respondents shall take with respect to the Site shall pertain to the three designated disposal areas which are identified in Figure 1 attached hereto: Area A, Area B, and Area C.

Two operable units have been defined for the Site. Operable unit I, which is the Source Control Operable Unit ("SCOU"), is intended to address waste refuse and sub-surface soils at disposal area A and the two smaller disposal areas B and C. Operable unit II, which is the Groundwater Control Operable Unit ("GCOU"), is intended to address the contaminated groundwater at the Site. This SCW details the work that is required in connection with the SCOU.

The major components of the remedial action for the Site that shall be designed and implemented by the Respondents are the following: Waste Consolidation; Landfill Cover; <u>In-situ</u> Vapor Extraction of Waste Refuse and sub-Surface Soils. The Respondents are required to initiate and/or accomplish these remedial actions within the time periods specified herein and are required to submit reports as identified in Section III below.

The standards and specifications for each component of the remedial action which the Respondents shall implement are as follows:

(1) Cleanup Standard

- A. Cleanup Standard for the Waste and Sub-Surface Soils
- 1. The Respondents shall design, construct, operate, implement and maintain an <u>In-situ</u> Vapor Extraction ("ISVE") cleanup action in the contaminated Waste Refuse and sub-Surface Soils ("Waste/sub-Soils") of disposal area A (which area is identified in Figure 1 attached to the SOW). The Respondents shall operate the ISVE systems until the soil-gas cleanup standards specified pursuant to paragraph A.2., below, are met in the

contaminated Waste/sub-Soils. The Respondents shall use the soil-gas as the medium to determine the Cleanup Standard for the Site.

The Respondents shall fully operate, maintain, and implement the ISVE systems for at least two (2) years based on the design parameters specified by U.S. EPA after the Pilot-Scale Test. Within ninety (90) days after the two year anniversary of the commencement of full-scale operation of the ISVE system, the Respondents shall submit to U.S. EPA a state-of-the-art Groundwater/Soil-gas Model (the "Model") for each Volatile Organic Compound ("VOC") detected in the Waste/sub-Soils and/or the groundwater during the remedial investigation ("RI") to provide U.S. EPA with the data on which to base a soil-gas cleanup level in the Waste/sub-Soils. The Model shall be used to determine the concentration of VOCs in the Waste/sub-Soils necessary to achieve the protective level of WCs in the groundwater, as will be determined in the Record of Decision to be developed in connection with the Groundwater Control Operable Unit. The Respondents shall utilize all of the data produced during the Pilot-Scale Test, the two-year period of full-scale ISVE operation, as well as all previous sampling and monitoring activities to develop the Model. The soil-gas cleanup level designated by the U.S. EPA, to be determined based upon the Model, and the underlying data developed in connection with the formulation of the Model, and the clean-up level determined in the Record of Decision for the Groundwater Control Operable Unit must be achieved in order to eliminate source area contaminant loading to the aquifer, and is intended to assure that the Cleanup Standards for the Groundwater are met.

In the event that the Respondents can establish to the satisfaction of the U.S. EPA, in consultation with the State, that it is appropriate for Respondents to develop and submit the Model to U.S. EPA before the two-year anniversary deadline specified above, then the Respondents shall submit the Model upon receipt of written approval from U.S. EPA. At the time the Respondents request approval to submit the Model prior to the two-year anniversary deadline, Respondents shall submit to U.S. EPA and the State all data relied upon by the Respondents to support their belief that such early submission is appropriate, as well as any other data requested thereafter by U.S. EPA, in consultation with the State.

Upon receipt of the state-of-the-art Model, the assumptions used for the Model, the data utilized to develop the Model, and the resulting soil-gas concentration for each VOC determined by the Model, the U.S. EPA, in consultation with the State, will review the Model and the resulting soil-gas concentrations to determine whether the model-produced soil-gas concentrations are appropriate for use as the Cleanup Standard for the contaminated Waste/sub-Soils. If the U.S. EPA, in consultation with the State, finds that the selection and/or use of the Model, the assumed input parameters, the data relied upon, and the resultant soil-gas concentration for each VOC are inappropriate or inadequate, then within thirty (30) days after receiving written comments from the U.S. EPA (prepared in consultation with the State) the Respondents shall revise or reselect or reperform the Model according to the review comments provided by the U.S. EPA, and shall submit to the U.S. EPA for approval, in consultation with the State, the revised Model. If the U.S. EPA, in consultation with the State, requests that more data be developed by the Respondents in order to perform the Model, the Respondents shall conduct

such additional sampling or monitoring activities as requested by the U.S. EPA, in consultation with the State.

If the revised groundwater/soil-gas Model, the assumed Model parameters, the resultant soil-gas concentration, and the additional sampling or monitoring data are not approved by the U.S. EPA, in consultation with the State, then the U.S. EPA, in consultation with the State, shall provide the type of the Model, the assumed model-parameters, and the resultant soil-gas concentration to the Respondents as the Cleanup Standard for the Site. The soil-gas concentration provided by the U.S. EPA, in consultation with the State, shall be used as the Cleanup Standard for the contaminated Waste/sub-Soils.

U.S. EPA, in consultation with the State, has the sole discretion to determine the soil-gas Cleanup Standard.

The Settling Defendants shall operate, maintain, and implement the ISVE system until they achieve the level of reduction of VOCs determined to be the Cleanup Standard.

B. Determination of Final soil-gas concentration of VOCs

No less than ninety (90) days prior to commencing the sampling necessary to determine the final soil-gas concentration of the VOCs in the Waste/sub-Soils within disposal area A, Respondents shall submit to U.S. EPA and the State, for approval by U.S. EPA, in consultation with the State, a Field Sampling Plan and Quality Assurance Project Plan (QAPP) for the determination of such final Soil-gas concentration of VOCs. The Field Sampling Plan shall at a minimum include the duration and frequency of sampling activity, the vertical and horizontal locations of sampling, the method of sampling and analysis, the compounds to be analyzed, and the method to compute the final soil-gas concentration for each VOC. In the event that the Respondents determine that it is necessary to temporarily shutdown the operation of the ISVE system in order to collect samples in connection with determining the final soil-gas concentration for VOCs in the Waste/sub-Soils within disposal area A, then the Respondents shall first obtain the approval of the U.S. EPA, in consultation with the State, for such temporary shutdown. Immediately upon completion of such sampling, the Respondents shall reactivate the ISVE system. Upon approval of the Field Sampling Plan and QAPP by U.S. EPA, in consultation with the State, the Respondents shall implement the sampling and testing required under the Field Sampling Plan. The Respondents shall prepare a Final Soil-gas Report, which shall be submitted to U.S. EPA and the State, for approval by U.S. EPA (in consultation with the State), detailing the results of the field sampling and monitoring analysis. Upon request of U.S. EPA or the State, Respondents shall submit to U.S. EPA and the State the test results and underlying data compiled in connection with the sampling and testing performed pursuant to the Field Sampling Plan. The Final Soil-gas Report shall document the final soil-gas concentration of each VOC in the Waste/sub-Soils at disposal area A.

C. Pilot-Scale Test

After excavation of the non-native materials from disposal areas B and C and consolidation of such materials in disposal area A (pursuant to Section II(2), below, of the SOW), and after construction of the landfill cover (pursuant to Section II(3), below, of the SOW), but prior to full-scale implementation of the ISVE system, the Respondents shall design and implement a pilot-scale test of ISVE of the VOCs in disposal area A (the "Pilot-Scale Test"). The Respondents, pursuant to the time table established in Section IV, below, of the SOW, shall submit, to U.S. EPA and the State, a work plan for conducting the Pilot-Scale Test for ISVE, which is subject to approval by U.S. EPA, in consultation with the State. The work plan shall include, at a minimum, the location within disposal area A where the Pilot-Scale Test is to be conducted, the operation parameters, i.e., number of extraction wells, pumping rate, etc., to be used during the Pilot-Scale Test, and the time necessary to conduct and complete the Pilot-Scale Test. The work plan shall be approved by the U. S. EPA, in consultation with the State. At the conclusion of the Pilot-Scale Test, the Respondents shall present the results of the Pilot-Scale Test to the U.S. EPA and the State. The underlying data developed during the Pilot-Scale Test shall be made available to the U.S. EPA and the State promptly at the request of the U.S. EPA or the State. The Pilot-Scale Test shall determine the most efficient design parameters for full-scale implementation of ISVE in disposal area A. The design parameters shall include, at a minimum, the number of extraction and injection wells, spacing between wells, extraction pumping rate, and off-gas treatment requirements.

The Respondents shall conduct sampling activities to characterize the physical parameters of the Waste/sub-soils, including, but not limited to, moisture content, grain size distribution, and total organic carbon. As part of the Pilot- Scale Test Work Plan, Respondents shall include the sampling plan necessary to conduct this sampling activity.

(2) Waste Consolidation

The Respondents shall excavate the non-native materials, which includes municipal wastes and associated contaminated soils, as well as any industrial debris which may be found, from disposal areas B and C (which is identified in Figure 1 attached to the SOW). The excavated materials shall be consolidated in disposal area A. Prior to commencing excavation, the Respondents shall develop and submit to the U.S. EPA for approval, in consultation with the State, a Field Operating Plan which shall include, at a minimum, the exact boundaries of disposal areas B and C to be excavated, the method of defining the non-native materials excavated from disposal area B and C, the location within disposal area A where the excavated materials are to be consolidated, and the method to be used to fill and landscape (with vegetation native to the area) the excavated depression areas within disposal areas B and C. The Respondents shall commence the waste consolidation activity within thirty (30) days after receiving from U.S. EPA, in consultation with the State, approval of the Field Operating Plan.

The Respondents shall also develop and submit to the U.S. EPA for approval, in consultation with the State, a Contingency Plan to deal with

discovery of unexpected wastes, such as barrels of solvents, contaminated waste, or contaminated soils, during the excavation of disposal areas B and C.

(3) Landfill Cover

The Respondents shall design, install, operate, and maintain a landfill cover in the disposal area A in order to reduce or minimize release of contaminants to the groundwater. The landfill cover shall be designed and installed to meet or exceed the requirements of Wisconsin Administrative Code NR 504.07(1)-(7). The landfill cover shall include (from top to bottom):

- The top layer shall consist of a vegetative layer a minimum of 6 inches thick that will sustain plant growth and will reduce erosion and promote drainage
- A soil layer a minimum of 18 inches thick
- A gravel drainage layer a minimum of 1.0 foot thick that will minimize infiltration into the low permeability layer
- The bottom layer shall be a low permeability, compacted clay layer that minimizes infiltration. This layer shall be a minimum of 2.0 feet thick and shall have a maximum hydraulic conductivity of 1 X 10-7 cm/s

The landfill cover shall be constructed after the consolidation of the non-native materials from areas B and C within area A, but prior to the Pilot-Scale Test (Section II(1)(D), above) and full-scale implementation of ISVE discussed in Section II(4), below. The Respondents shall maintain the integrity of the landfill cover during the ISVE Pilot-Scale Test and implementation of the ISVE cleanup action.

The Respondents shall develop and submit to the U.S. EPA for approval, in consultation with the State, a Sampling and Testing Plan to test clay materials for hydraulic conductivity. The Sampling and Testing Plan shall also include the source and type of clay materials that shall be used for the landfill cover. The Respondents shall conduct such sampling and testing within thirty (30) days after receiving from U.S. EPA, in consultation with the State, approval of the Sampling and Testing Plan.

Upon written request of the U.S. EPA, in consultation with the State, the Respondents shall initiate construction of the landfill cover after submitting to U.S. EPA the prefinal design, but before submission and approval of the final design.

(4) Implementation of <u>In-situ</u> Vapor Extraction of Waste Refuse and Sub-Surface Soils

Subsequent to the excavation and consolidation of non-native materials from disposal areas B and C to disposal area A, and installation of the landfill cover over disposal area A, the Respondents shall implement an ISVE system in order to cleanup the contaminated Waste/sub-Soils within disposal

area A. The ISVE system shall consist of installation of extraction and injection wells for the Waste/sub-Soils area, and treating off-gas which is emitted from the extraction wells. The ISVE shall be proceeded by a Pilot-Scale Test (see Section II(1)(C), above) prior to full-scale implementation.

A. Full-scale ISVE Implementation

After the completion of the Pilot-Scale Test, the Respondents shall implement the full-scale ISVE of the Waste/sub-Soils in disposal area λ until the Waste/sub-Soils Cleanup Standard identified in Section II(1)(λ), above, is met. During the course of the ISVE implementation, if either the Respondents or U.S. EPA determine that the removal of VOCs can be enhanced by pulsing either the entire ISVE system or individual wells, U.S. EPA may, at its option, require the Respondents to operate the system in that manner.

During the first six months after initiating the full-scale ISVE system, the Respondents shall perform a study to examine the feasibility of adding essential nutrients (e.g., moisture, nitrogen, and phosphate) to the Waste/sub-Soils in disposal area A in order to enhance the natural microbial degradation of organic compounds (the "Feasibility Test"). The Feasibility Test shall be subject to the supervision and review of the U.S. EPA, in consultation with the State. The objective of the Feasibility Test is to determine the optimum amounts of nutrients to be added to the Waste/sub-Soils in order to promote the natural microbial activities, without decreasing the effectiveness of the removal of the VOCs by ISVE. At the conclusion of the Feasibility Test period, the Respondents shall present the results of this study to the U.S. EPA and the State in the form of a written report. The underlying data developed during the Feasibility Test shall be made available to the U.S. EPA and the State at the request of the U.S. EPA or the State. Based on the results of the Feasibility Test, U.S. EPA, in consultation with the State, may require the Respondents to implement the addition of essential nutrients to the Waste/sub-Soils.

The Respondents shall describe the method of conducting the Feasibility Test in the Remedial Design.

B. Off-gas Treatment

The Respondents shall design, construct, operate, and maintain a carbon adsorption system to treat off-gases emitted from the extraction wells both during the pilot-scale test and the full-scale implementation of ISVE. The Respondents shall treat off-gas emitted from the extraction wells using a carbon adsorption system in order to meet the requirements of the Wisconsin Administrative Code, NR 445, Control of Hazardous Pollutants. The Respondents shall submit to the U.S. EPA and the State the air emission monitoring program, specifying the frequency, duration, and compounds to be analyzed. Such program shall be subject to approval by the U.S. EPA, in consultation with the State.

The Respondents shall send the spent carbon or other residues produced from off-gas treatment back to the manufacturer to be regenerated.

C. Notification of Temporary ISVE Shutdown

If, for any reason during the period of operation of the ISVE system, including the Pilot-Scale Test period, the operation of the ISVE system is interrupted or stopped, whether due to mechanical failure, human error, or any other reason (except for routine maintenance), then the Respondents shall notify the U.S. EPA and the State of such interruption or cessation of operation within twenty-four (24) hours after learning thereof. Such notification may initially be given orally, but must be confirmed in writing within five days after the date on which the oral notification is given. The Respondents shall notify U.S. EPA and the State of the nature and cause of the interruption or cessation of operation, as well as the estimated length of time before the operation of the ISVE system will be resumed.

If, for any reason during the period of operation of the ISVE system, including the Pilot-Scale Test period, the Respondents determine that it is necessary to temporarily interrupt the operation of the ISVE system in order to perform routine maintenance on the system (i.e., replace spent carbon, parts, or any other necessary maintenance), then the Respondents shall give U.S. EPA and the State a minimum of forty-eight (48) hours notice, in writing, prior to such shutdown. The Respondents shall notify the U.S. EPA and the State of the nature of the maintenance to be performed, as well as the estimated length of time before the operation of the ISVE system will be resumed.

In all cases where there is an interruption or cessation in the operation of the ISVE system, whether due to mechanical failure, human error, or to perform routine maintenance, as well as any other reason, the Respondents shall use their best efforts to repair, complete maintenance, or take any other steps necessary to timely resume the operation of the ISVE system.

D. Termination of Operation

The Respondents shall operate the ISVE system until the Waste/sub-Soils Cleanup Standard is met. Upon achieving the Cleanup Standard, Respondents shall submit to U.S. EPA and the State for review and approval by U.S. EPA, in consultation with the State, a Draft Remedial Action Report containing the data establishing that the Cleanup Standard has been achieved. Respondents may terminate the operation of the ISVE system only upon the express written approval of the U.S. EPA, in consultation with the State. Upon termination of the ISVE system, Respondents shall remove all equipment used at the Site in connection with the ISVE system, and shall fill and grade all well extraction points, trenches, etc., prepared in connection with the operation of the ISVE system.

(5) Fence Installation

The Respondents shall implement and maintain fencing of the Site to reduce risks which may be posed to public health due to construction activity or exposure to hazardous chemicals at the Site during the cleanup process and to also protect treatment equipment from vandalism. The fence shall consist

of a six-foot high chain link perimeter fence topped with three-strand barbed wire. The fence shall enclose disposal areas A, B, and C shown in Figure 1, and shall be equipped with a swing gate at the entrance to the access road. Standard Superfund warning signs shall be posted at 200-foot intervals along the fence and on the gate. Once the operation has been terminated, the Site shall be sufficiently fenced to prevent its further use as a dump or motorized vehicle track, but not to restrict pedestrian or wildlife access.

(6) Institutional Controls

The Respondents shall continue to comply with State regulations prohibiting future development of the Site, as set forth in Section NR 504.07(8) (a-c), WAC, and in Section NR 506.08(5), WAC as well as the State regulations prohibiting the installation of drinking water wells within 1200 feet of a landfill, as set forth in Section NR 112.08(4)(g), WAC.

Within 60 days after receiving the Administrative Order in this matter, the Owner Respondent shall file deed restrictions with register deed for Dane County, Wisconsin applicable to all property owned by Owner Respondent at the Site prohibiting: 1) any consumptive or other use of the groundwater underlying the Site that could cause exposure to humans or animals; 2) any use of, or activity, at the Site that may interfere with the work to be performed at the Site as required by the Administrative Order; and 3) any residential or commercial use of the Site, including but not limited to any filling, grading, excavating, building, drilling, mining, farming, or other development, or placing waste material at any portion of the Site, except with the approval of U.S. EPA, in consultation with the State, as consistent with the requirements of the Administrative Order.

Within 60 days after receiving the Administrative Order in this matter, the Respondents shall obtain all additional easements, deed restrictions, land use limitations, or other enforceable instruments restricting private property use necessary to prevent interference with and complete the work on property other than that owned by Owner Respondent at the Site.

(7) Access

Respondents shall secure access to the Site for the purpose of implementing work required by the Administrative Order and this SOW, including the installation and operation and maintenance of the cap, Site fence, ISVE, excavation for sampling, extraction, and treatment, on those portions of the Site or its surroundings not presently owned by Respondents, as well as those portions owned by Respondents. Access to the Site and any other property to which access is necessary to implement this SOW shall be provided for representatives of the Respondents, as well as U.S. EPA and the State and their contractors or representatives.

III. SCOPE

The RD and RA Work Plan shall consist of four tasks:

Task I: RD and RA Work Plan

Task II: Remedial Design

- A. Design Plans and Specifications
- B. Operation and Maintenance Plan
- C. Cost Estimate
- D. Project Schedule
- E. Construction Quality Assurance Objectives
- F. Health and Safety Plan
- G. Design Phases
- H. Community Relations Support

Task III: Remedial Action Construction

- A. Responsibility and Authority
- B. Construction Quality Assurance Personnel Qualifications
- C. Inspection Activities
- D. Sampling Requirements
- E. Documentation

Task IV: Reports

- A. Progress
- B. Draft
- C. Final

Task I: RD and RA WORK PLAN

A. RD/RA Work Plan.

The Respondents shall prepare and submit to the U.S. EPA for approval, in consultation with the State, in accordance with the schedule set forth in Part IV below, an RD work plan which describes the overall management strategy for the landfill cover, pilot-scale testing of ISVE in disposal area A, and for the design phase of the overall cleanup remedy. A schedule for Waste/sub-Soils sampling, Waste consolidation, pilot-scale testing, and remedy implementation shall be included in the RD work plan. The RD work plan, which is a portion of the RD/RA work plan, is due within 45 days after receiving of the Administrative Order. The RD work plan shall include, but not be limited to, the following:

- 1. A Field Operating Plan for Waste Consolidation;
- A Contingency Plan for Waste Consolidation;
- A Sampling and Testing Plan for Clay.

The Respondents shall prepare and submit to the U.S. EPA for approval, in consultation with the State, in accordance with the schedule set forth in Part IV below, an RA work plan which shall describe the overall management strategy for performing the construction, operation and maintenance, and monitoring of the remedial action. The plan shall describe the responsibility and authority

of all organizations and key personnel involved with the implementation of the work required under the Administrative Order and this SOW.

Each portion of the RA work plan shall also include the name(s) and a description of qualifications of key personnel directing the RD/RA, including contractor personnel.

Task II: REMEDIAL DESIGN

The Respondents shall prepare and submit to U.S. EPA for approval, in consultation with the State, final construction plans and specifications to implement the Remedial Actions at the Site as defined in the "Purpose" and the "Description of the Remedial Action" section of this SOW.

As indicated in the schedule for the submission of design plans and other documents, Section IV. below, the Respondents are required to submit the design and implementation plans for the landfill cover under a schedule separate and apart from the schedule for the submission of design and implementation of the ISVE system. Each design and implementation submittal shall contain the items described below in Section III.

A. Design Plans and Specifications

The Respondents shall develop and submit to U.S. EPA for approval, in consultation with the State, clear and comprehensive design plans and specifications which include but are not limited to the following:

- 1. Discussion of the design strategy and the design basis, including:
 - a. Compliance with all applicable and all relevant and appropriate environmental and public health laws, rules, regulations and standards; and
 - b. Minimization of environmental and public impacts.
- 2. Discussion of the technical factors of importance to the design and construction including:
 - a. Use of currently accepted environmental control measures and technology;
 - b. The constructability of the design; and
 - c. Use of currently acceptable construction practices and techniques.
- 3. Description of assumptions made and detailed justification of these assumptions;
- 4. Discussion of the possible sources of error and references to possible operation and maintenance problems;

- 5. Detailed drawings of the proposed design including;
 - a. Qualitative flow sheets; and
 - b. Quantitative flow sheets.
- 6. Tables listing equipment and specifications;
- 7. Tables giving material and energy balances;
- 8. Appendices including;
 - a. Sample calculations (one example presented and explained clearly for significant or unique design calculations);
 - b. Derivation of equations essential to understanding the report;
 - c. Results of the Waste/sub-Soils Sampling Program; and
 - d. Results of the Pilot-Scale Test.

B. Operation and Maintenance Plan

The Respondents shall prepare and submit to U.S. EPA for approval, in consultation with the State, an Operation and Maintenance Plan to cover both implementation and long term maintenance of the Remedial Actions. The plan shall be composed of the following elements:

- 1. Description of normal operation and maintenance (OWM), including;
 - a. Description of tasks for operation;
 - b. Description of tasks for maintenance;
 - c. Description of prescribed treatment or operation conditions; and
 - d. Schedule showing frequency of each OWM task.
- 2. Description of potential operating problems, including;
 - Description and analysis of potential operation problems;
 - b. Sources of information regarding problems; and
 - c. Common and/or anticipated remedies.
- 3. Description of routine monitoring and laboratory testing, including:
 - a. Description of monitoring tasks;

- c. Records for operating costs;
- d. Mechanism for reporting emergencies;
- e. Personnel and maintenance records; and
- f. Monthly/annual reports to State agencies.

An initial Draft Operation and Maintenance Plan shall be submitted by Respondents to U.S. EPA simultaneously with the Prefinal Design Document submission and the Final Operation and Maintenance Plan with the Final Design Documents.

The Respondents shall submit to U.S. EPA for approval, in consultation with the State, updates of the final Operation and Maintenance Plan after construction of each component of the remedial action in order to reflect any changes necessitated by the construction.

C. Cost Estimate

The Respondents shall develop and submit to U.S. EPA for approval, in consultation with the State, cost estimates for the purpose of assuring that the Respondents have the financial resources necessary to construct and implement the Remedial Action. The cost estimate developed in the Feasibility Study shall be refined to reflect the more detailed/accurate design plans and specifications being developed. The cost estimate shall include both capital and operation and maintenance costs. An Initial Cost Estimate shall be submitted simultaneously with the Prefinal Design submission and the Final Cost Estimate shall be submitted along with the Final Design Document.

D. Project Schedule

The Respondents shall develop a Project Schedule for construction and implementation of the Remedial Actions. The Project schedule shall identify timing for initiation and completion of all critical path tasks. Respondents shall specifically identify dates for completion of the project and major interim milestones. An Initial Project Schedule shall be submitted simultaneously with the Prefinal Design Document submission and the Final Project Schedule shall be submitted along with the Final Design Document. The Final Project Schedule is subject to review and approval by the U.S. EPA, in consultation with the State.

E. Construction Quality Assurance Objectives

The Respondents shall identify and document the objectives and framework for the development of a construction quality assurance program including, but not limited to the following: responsibility and authority; personnel qualifications; inspection activities; sampling requirements; and documentation.

F. Health and Safety Plan

The Respondents shall modify and submit to U.S. EPA for approval, in consultation with the State, the Health Safety Plan developed for the RI/FS to address the activities to be performed at the facility to implement the Remedial Action(s).

G. <u>Design Phases</u>

The design of the Remedial Action(s) shall include the phases outlined below.

1. Preliminary design

The Respondents shall submit the Preliminary Design when the design effort is approximately 30% complete. At this stage, the Settling Defendants shall have field verified the existing conditions of the facility. The Preliminary Design shall reflect a level of effort such that the technical requirements of the project have been addressed and outlined so that they may be reviewed to determine if the final design will provide an operable and usable Remedial Action. The Respondents shall provide supporting data and documentation with the Design Documents defining the functional aspects of the program. The preliminary construction drawings by the Respondents shall reflect organization and clarity. The scope of the technical specifications shall be outlined in a manner reflecting the final specifications. The Respondents shall include with their preliminary design submission, calculations reflecting the same percentage of completion as the designs they

2. Correlating plans and specifications

General correlation between drawings and technical specifications is a basic requirement of any set of working construction plans and specifications. Before submitting the project specifications, the Respondents shall:

- a. Coordinate and cross-check the specifications and drawings; and
- b. Complete the proofing of the edited specifications and the cross-checking of all drawings and specifications.

These activities shall be completed prior to the 95% prefinal submittal to the U.S. EPA and the State.

Equipment start-up and operator training

The Respondents shall prepare, and include in the technical specifications governing treatment systems, contractor

requirements for providing appropriate service visits by experienced personnel to supervise the installation, adjustment, start up and operation of the treatment systems, and training covering appropriate operational procedures once the startup has been successfully accomplished.

4. Additional studies

The U.S. EPA, in consultation with the State, may require the Respondents to conduct additional studies to supplement the available technical data. At the discretion and under the direction of the U.S. EPA for any such studies required, the Settling Defendants shall furnish all services, including field work as required, materials, supplies, plant, labor, equipment, investigations, studies and superintendence. The Respondents shall perform sufficient sampling, testing and analysis to optimize the required treatment and/or disposal operations and systems. There shall be an initial meeting of all principal personnel with the Respondents involved in the development of the program. The purpose of the meeting will be to discuss objectives. resources, communication channel, role of personnel involved and orientation of the Site. The interim report shall present the results of the testing with the recommended treatment or disposal system (including options). A review conference shall be scheduled after the interim report has been reviewed by all interested parties. The Respondents' final report of the testing shall include all data taken during the testing and a summary of the results of the studies.

5. Prefinal and Final Design

The Respondents shall submit to the U.S. EPA for approval, in consultation with the State, the Prefinal/Final design documents in two parts. The first submission shall be the "prefinal" submission which shall be submitted at 95% completion of design. After review and approval of the prefinal submission by the U.S. EPA, in consultation with the State, the Respondents shall execute any required revisions and submit the final documents to the U.S. EPA 100% complete with reproducible drawings and specifications.

The Prefinal Design submittal shall contain the Design Plans and Specifications, Operation and Maintenance Plan, Capital and Operating and Maintenance Cost Estimate, Project Schedule, Quality Assurance Project Plan and the Health and Safety Plan.

The Final Design submittal contain the Final Design Plans and Specifications (100% complete), the Respondents' Final Construction Cost Estimate, the Final Operation and

Maintenance Plan, Final Quality Assurance Project Plan, Final Project Schedule and Final Health and Safety Plan. The quality of the design documents should be such that the Respondents would be able to include them in a bid package and invite contractors to submit bids for the construction project.

H. Community Relations Support

A community relations program will be implemented by the U.S. EPA, in consultation with the State. The Respondents shall cooperate with the U.S. EPA and the State by participating in the preparation of all appropriate information disseminated to the public, and in public meetings that may be held or sponsored by the U.S. EPA or the State to explain activities at, or concerning, the Site, including, but not limited to the findings of the Waste/sub-Soils Sampling Program and the Pilot-Scale Test.

The community relations support which the Respondents shall be required to undertake should be consistent with Superfund community relations policy as stated in the "Guidance for Implementing the Superfund Program" and "Community Relations in Superfund - A Handbook".

TASK III: REMEDIAL ACTION CONSTRUCTION

Following U.S. EFA approval of the final design, the Respondents shall develop and implement a construction quality assurance (CQA) program to ensure, with a reasonable degree of certainty, that the completed Ramedial Action meets or exceeds all design criteria, plans and specifications. The CQA plan should be prepared specifically for the Hagen Farm Site. This plan shall be submitted to the U.S. EFA for approval, in consultation with the State, prior to the start of the construction. At a minimum, the CQA plan shall include the elements, which are summarized below as Section III Subpart, A through E. Upon U.S. EFA approval of the CQA Plan the Respondents shall construct and implement the Remedial Actions in accordance with the approved design, schedule, and the CQA plan. The Respondents shall also implement the elements of the approved operation and maintenance plan.

A. Responsibility and Authority

For the CQA plan, the Respondents shall describe fully the responsibility and authority of all organizations (i.e. technical consultants, construction firms, etc.) and key personnel involved in the construction of the corrective measure shall be described fully in the CQA plan. The Respondents shall also identify a CQA officer and the necessary supporting inspection staff.

B. <u>Construction Quality Assurance Personnel Qualifications</u>

The qualifications of the CQA officer and supporting inspection personnel shall be presented in the CQA plan in order to demonstrate

that they possess the training and experience necessary to fulfill their identified responsibilities.

C. Inspection Activities

The Respondents shall summarize in the CQA plan the observations and tests that will be used to monitor the construction and/or installation of the components of the Remedial Actions. The plan shall include the scope and frequency of each type of inspection. Inspections shall verify compliance with the environmental requirements and include, but not be limited to, air quality and emissions monitoring records, waste disposal records (e.g., RCRA transportation manifests). The inspection shall also ensure compliance with all health and safety procedures. In addition to oversight inspections, the Respondents shall conduct the following activities.

1. Preconstruction inspection and meeting

Prior to initiating or commencing, the Respondents shall conduct a remedial action construction inspection and meeting to:

- a. Review methods for documenting and reporting inspection data;
- b. Review methods for distributing and storing documents and reports;
- c. Review work area security and safety protocol;
- d. Discuss any appropriate modifications of the construction quality assurance plan to ensure that site-specific considerations are addressed; and
- e. Conduct a site walk-around to verify that the design criteria, plans, and specifications are understood and to review material and equipment storage locations.

The preconstruction inspection and meeting shall be documented by a designated person and minutes shall be transmitted to U.S. EPA and the State within fourteen (14) days after the meeting.

2. Prefinal inspection

Upon preliminary project completion, the Respondents shall notify U.S. EPA for the purposes of conducting a prefinal inspection. The prefinal inspection shall consist of a walk-through inspection of the entire project site. The inspection is to determine whether the project is complete and consistent with the contract documents and the EPA approved Remedial Action. Any outstanding construction items discovered during the inspection shall be identified and noted. Additionally, treatment equipment shall be operationally tested by Respondents. The Respondents shall certify that the equipment has performed to meet the purpose and intent of the specifications. Retesting will be completed where deficiencies are revealed. The prefinal inspection report shall outline

the outstanding construction items, actions required to resolve items, completion date for these items, and date for final inspection.

3. Final inspection

Upon completion of any outstanding construction items, the Respondents shall notify EPA for the purposes of conducting a final inspection. The final inspection shall consist of a walk-through inspection of the project site. The prefinal inspection report will be used as a checklist with the Final inspection focusing on the outstanding construction items identified in the prefinal inspection. Confirmation shall be made that outstanding items have been resolved.

D. <u>Sampling Requirements</u>

The sampling activities, sample size, sample locations, frequency of testing, acceptance and rejection criteria, and plans for correcting problems as addressed in the project specifications shall be presented in the CQA plan.

E. <u>Documentation</u>

Reporting requirements for CQA activities shall be described in detail in the CQA plan. This shall include such items as daily summary reports, inspection data sheets, problem identification and corrective measures reports, design acceptance reports, and final documentation. Provisions for the final storage of all records shall be presented in the CQA plan.

TASK IV: Reports and Submissions

The Respondents shall prepare and submit to U.S. EPA and the State plans, specifications, and reports as set forth in Tasks I through Task IV to document the design, construction, operation, maintenance, and monitoring of the Remedial Action. The documentation shall include, but not be limited to the following:

A. Progress

The Respondents shall at a minimum provide the U.S. EPA and the State with signed monthly progress reports during the design and construction phases and semi-annual progress reports for operation and maintenance activities containing:

- 1. A description and estimate of the percentage of the RD/RA completed;
- Summaries of all findings;
- 3. Summaries of all changes made in the RD/RA during the reporting period;

- 4. Summaries of all contacts with representative of the local community, public interest groups, and/or State government during the reporting period;
- 5. Summaries of all problems or potential problems encountered during the reporting period;
- 6. Actions being taken to rectify problems;
- 7. Changes in personnel during the reporting period;
- 8. Projected work for the next reporting period; and
- 9. Copies of daily reports, inspection reports, laboratory/monitoring data, etc.

B. Draft

- 1. The Respondents shall submit to U.S. EPA and the State a draft RD Work Plan and a draft RA Work Plan as outlined in Task I;
- 2. The Respondents shall submit to U.S. EPA and the State draft construction Plans and Specifications, Design Reports, Cost Estimates, Schedules, Operation and Maintenance plans, and Study Reports as outlined in Task II;
- 3. The Respondents shall submit to U.S. EPA and the State a draft construction Quality Assurance Program Plan and documentation as outlined in Task III; and
- 4. At the completion of the construction of the project, the Settling Defendants shall submit to U.S. EPA and the State a Remedial Action Implementation Report. The Report shall certify that the project is consistent with the design specifications, and that Remedial Action is performing adequately. The Report shall provide or specifically reference all documents or material which support the statements contained in the Report. The Report shall include, but not be limited to the following elements:
 - a. Synopsis of the Remedial Action and certification of the design and construction;
 - b. Explanation of any modifications to the plans and why these were necessary for the project;
 - c. Listing of the criteria, established before the Remedial Action was initiated, for judging the functioning of the Remedial Action and also explaining any modification to these criteria;

- d. Results of facility monitoring, indicating that the Remedial Action will meet or exceed the performance criteria;
- e. Explanation of the operation and maintenance (including monitoring) to be undertaken at the facility; and

C. Final

The Respondents shall finalize the RD and RA work plans, Design Reports, Construction Plans and Specifications, Cost Estimates, Project Schedule, Operation and Maintenance Plan, Study Reports, Construction Quality Assurance Program Plan/Documentation and the Remedial Action Implementation Report incorporating comments received from U.S. EPA and the State on draft submissions.

IV SUBMISSION SUMMARY

· The Respondents' RD and RA work plans shall comply with the following time table information reporting requirements:

Submission Due Date 45 days after the receipt of Draft RD/RA Work Plan (Task I) Administrative Order 30 days after U.S. EPA Final RD/RA Work Plan (Task I) comments on draft RD/RA Work Plan. Design Phases for Landfill Cover (Task II) Prefinal Design (95% completion) 80 days after the receipt of Administrative Order. Final Design (100% completion) 30 days after U.S. EPA comments on the Prefinal Design Concurrent with Prefinal Design of Draft Submittals Landfill Cover. Construction Designs and Specifications Design Reports Cost Estimates RA Project Schedules Operation and Maintenance Plan Construction Quality Assurance Objectives Health and Safety Plan Operation and Maintenance QAPP Final Submittals Concurrent with Final Design of Landfill Cover. Construction Designs and Specifications Design Reports Cost Estimates RA Project Schedules Operation and Maintenance Plan Construction Quality Assurance Objectives Health and Safety Plan Operation and Maintenance QAPP Draft Construction Quality Concurrent with Prefinal Assurance Plan (Task III) design of Landfill Cover Final Construction Quality Concurrent with Final Assurance Plan design of Landfill Cover Construction of Remedial Action As approved in Final Design.

30 days after Prefinal Inspection

Prefinal Inspection Report

30 days after Final Inspection

Final Inspection Report

Draft Remedial Action Upon completion of construction phase. Implementation Report (Task IV) Completion of Construction As approved by U.S. EPA in the RD and RA Work Plans. Final Remedial Action 30 days after U.S. EPA comment on Draft Remedial Action Implementation Report (Task IV) Implementation Report. O & M Plan Revision 30 days after Final Remedial Action Implementation Report Draft Pilot-Scale Test 45 days after U.S. EPA Work Plan for ISVE approval on the final design for Landfill Cover Final Pilot-Scale Test 30 days after U.S. EPA Work Plan for ISVE comments on Draft Work Plan for Pilot-Scale Test. Draft Pilot-Scale Test 45 days after completing Pilot-Scale Test Report for ISVE activity Final Pilot-Scale Test 30 days after U.S. EPA Report for ISVE comments on Draft Pilot-Scale Test Report Design Phases for ISVE (Task II) Preliminary Design (30% completion) 60 days after U.S. EPA approval of the Final Pilot-Scale Test Report for ISVE Prefinal Design (95% completion) 120 days after U.S. EPA approval of the Final Pilot-Scale Test Report for ISVE Final Design (100% completion) 30 days after U.S. EPA approval of the prefinal design for ISVE Draft Submittals Concurrent with Prefinal Design of Construction Designs and Specifications

Design Reports
Cost Estimates
RA Project Schedules
Operation and Maintenance Plan
Construction Quality Assurance Objectives
Health and Safety Plan
Operation and Maintenance QAPP
Draft Feasibility Test Plan
Feasibility Test Plan
Air Emission Monitoring Program

Final Submittals

Concurrent with Final Design of ISVE.

Construction Designs and Specifications
Design Reports
Cost Estimates
RA Project Schedules
Operation and Maintenance Plan
Construction Quality Assurance Objectives
Health and Safety Plan
Operation and Maintenance QAPP
Feasibility Test Plan
Air Emission Monitoring Program

Draft Construction Quality Assurance Plan (Task III)

Final Construction Quality Assurance Plan (Task III)

Construction of Remedial Action

Prefinal Inspection Report

Final Inspection Report

Draft Remedial Action Implementation Report (Task IV)

Completion of Construction

Final Remedial Action
Implementation Report (Task IV)

Feasibility Test Report

Concurrent with Prefinal Design of ISVE

Concurrent with Final Design of ISVE

As approved in Final Design.

30 days after Prefinal Inspection

30 days after Final Inspection

Upon completion of construction phase.

As approved by U.S. EPA in the RD and RA Work Plans.

30 days after U.S. EPA comment on Draft Remedial Action Implementation Report.

30 days after completing Feasibility Test activity

Draft Groundwater/Soil-Gas Within 90 days after Model Submittal two year anniversary of the commencement of full-scale operation of ISVE Final Groundwater/Soil-Gas 30 days after U.S. EPA' Model Submittal comments on the Draft Model Submittal 0 & M Revisions 30 days after approval of Final Remedial Action Implementation Report. Draft Field Sampling Plan and QAPP No less than 90 days for Final Soil-gas Concentration prior to commencing sampling for determination of Final Soil-gas concentration Final Field Sampling Plan and QAPP 30 days after U.S. EPA' for Final Soil-Gas concentration comments on Draft Field Sampling Plan and QAPP Draft Remedial Action Report 30 days after achieving the Cleanup Standard Final Soil-Gas Report As specified and approved in Final Field Sampling Plan 30 days after approval of Draft Remedial Action Report

Final Remedial Action Report


Progress Reports for Tasks I through IV

Progress Reports during Operation and Maintenance Monthly

Semi-annually.

Figure 1 Site Diagram Hagen Farm Site Dunkirk Township, Wisconsin

(Not To Scale)





Prepared by Jacobs Engineering Group Inc. Chicago for the U.S. Environmental Protection Agency, 7/22/90

Drawn Checked HA DS